



# TECHNICAL DUE DILIGENCE SUMMARY REPORT ON PLANT CONFIGURATION

# RE Portfolio of Solar PV and CSP Projects



July 2023

P020230502



# Issue and Revision Record

| Ver. | Date     | Originator | Checker | Approver | Description  |
|------|----------|------------|---------|----------|--------------|
| 01   | 28/06/23 | HM         | SS      | PD       | Draft report |
| 02   | 11/07/23 | HM         | SS      | PD       | Final Report |
|      |          |            |         |          |              |

# Disclaimer

This document has been prepared for the proposed acquisition of the subject solar portfolio by India Grid Trust and related fund-raising by India Grid Trust (including for inclusion in any preliminary placement document, placement document, information memorandum, communication to unitholders, regulatory filings or any other document in connection with the acquisition by India Grid Trust and submitted to regulatory authorities, if required), and should not be relied upon or used for any other project without an independent check being carried out as to its suitability and prior written authority of TruBoard Credit Monitoring Services Private Limited ('TruBoard') being obtained. TruBoard accepts no responsibility or liability for the consequence of this document being used for a purpose other than those for which it was commissioned. Any person using or relying on the document for such other purpose will by such use or reliance be taken to confirm his agreement to indemnify TruBoard for all loss or damage resulting therefrom. TruBoard accepts no responsibility or liability for this document to any party other than the person by whom it was commissioned. This report may be relied upon by the placement agents and other advisors to India Grid Trust in connection with the above purpose.

To the extent that this report is based on information supplied by other parties, TruBoard accepts no liability for any loss or damage suffered by the client, whether contractual or tortious, stemming from any conclusions based on data supplied by parties other than TruBoard and used by TruBoard in preparing this report.



# Table of Contents

| List of | Acronyms                  | 7  |
|---------|---------------------------|----|
| 1.      | Introduction              | 8  |
| 2.      | PLG Patan                 | 11 |
| 2.1.    | About Project             | 11 |
| 2.2.    | Technology                | 12 |
| 2.2.1.  | PV module                 | 12 |
| 2.2.2.  | Inverter                  | 13 |
| 2.2.3.  | Inverter Duty Transformer | 14 |
| 2.3.    | Project Design            | 14 |
| 2.3.1.  | DC Configuration          | 14 |
| 2.3.2.  | AC Configuration          | 15 |
| 2.4.    | Power evacuation          | 15 |
| 3.      | Terralight Charanka       | 16 |
| 3.1.    | About Project             | 16 |
| 3.2.    | Technology                | 18 |
| 3.2.1.  | PV module                 | 18 |
| 3.2.2.  | Inverter                  | 18 |
| 3.2.3.  | Inverter Duty Transformer | 19 |
| 3.3.    | Project Design            | 20 |
| 3.3.1.  | DC Configuration          | 20 |
| 3.3.2.  | AC Configuration          | 20 |
| 3.4.    | Power evacuation          | 20 |
| 4.      | Solar Edge Beed           | 21 |
| 4.1.    | About Project             | 21 |
| 4.2.    | Technology                | 22 |
| 4.2.1.  | PV modules                | 23 |
| 4.2.2.  | Inverter                  | 24 |
| 4.2.3.  | Inverter Duty Transformer | 24 |
| 4.3.    | Project Design            | 25 |
| 4.3.1.  | DC Configuration          | 25 |
| 4.3.2.  | AC Configuration          | 25 |
| 4.4.    | Power evacuation          | 26 |
| 5.      | Solar Edge Jalgaon        | 27 |
| 5.1.    | About Project             | 27 |



| 5.2.   | Technology                | .28 |
|--------|---------------------------|-----|
| 5.2.1. | PV module                 | .28 |
| 5.2.2. | Inverter                  | .29 |
| 5.2.3. | Inverter Duty Transformer | .30 |
| 5.3.   | Project Design            | .30 |
| 5.3.1. | DC Configuration          | .30 |
| 5.3.2. | AC Configuration          | .31 |
| 5.4.   | Power evacuation          | .31 |
| 6.     | Globus Mandsaur           | .32 |
| 6.1.   | About Project             | .32 |
| 6.2.   | Technology                | .34 |
| 6.2.1. | PV modules                | .34 |
| 6.2.2. | Inverter                  | .34 |
| 6.2.3. | Inverter Duty Transformer | .35 |
| 6.3.   | Project Design            | .35 |
| 6.3.1. | DC Configuration          | .35 |
| 6.3.2. | AC Configuration          | .36 |
| 6.4.   | Power evacuation          | .36 |
| 7.     | Terralight Patlasi        | .37 |
| 7.1.   | About Project             | .37 |
| 7.2.   | Technology                | .38 |
| 7.2.1. | PV modules                | .38 |
| 7.2.2. | Inverter                  | .39 |
| 7.2.3. | Inverter Duty Transformer | .40 |
| 7.3.   | Project Design            | .40 |
| 7.3.1. | DC Configuration          | .40 |
| 7.3.2. | AC Configuration          | .41 |
| 7.4.   | Power evacuation          | .41 |
| 8.     | Terralight Rajapalayam    | .42 |
| 8.1.   | About Project             | .42 |
| 8.2.   | Technology                | .44 |
| 8.2.1. | PV modules                | .44 |
| 8.2.2. | Inverter                  | .44 |
| 8.2.3. | Inverter Duty Transformer | .45 |
| 8.3.   | Project Design            | .45 |
| 8.3.1. | DC Configuration          | .45 |



| 8.3.2. | AC Configuration          | 46 |
|--------|---------------------------|----|
| 8.4.   | Power evacuation          | 46 |
| 9.     | Terralight Kanji          | 46 |
| 9.1.   | About Project             | 46 |
| 9.2.   | Technology                | 48 |
| 9.2.1. | PV modules                | 48 |
| 9.2.2. | Inverter                  | 49 |
| 9.2.3. | Inverter Duty Transformer | 50 |
| 9.3.   | Project Design            | 50 |
| 9.3.1. | DC Configuration          | 50 |
| 9.3.2. | AC Configuration          | 51 |
| 9.4.   | Power evacuation          | 51 |
| 10.    | UMD 25 MW (12 MW + 13 MW) | 52 |
| 10.1.  | About Project             | 52 |
| 10.2.  | Technology                | 54 |
| 10.4.  | Power evacuation          | 58 |
| 11.    | TN Solar Thuthookudi      | 58 |
| 11.1.  | About Project             | 58 |
| 11.2.  | Technology                | 60 |
| 11.3.  | Project Design            | 61 |
| 11.4.  | Power evacuation          | 62 |
| 12.    | TN Solar Virudhunagar     | 62 |
| 12.1.  | About Project             | 62 |
| 12.2.  | Technology                | 64 |
| 12.3.  | Project Design            | 65 |
| 12.4.  | Power evacuation          | 66 |
| 13.    | TN Solar Dindigul         | 67 |
| 13.1.  | About Project             | 67 |
| 13.2.  | Technology                | 68 |
| 13.3.  | Project Design            | 70 |
| 13.4.  | Power evacuation          | 71 |
| 14.    | USUPL Bap                 | 71 |
| 14.1.  | About Project             | 71 |
| 14.2.  | Technology                | 72 |
| 14.3.  | Project Design            | 74 |
| 14.4.  | Power evacuation          | 75 |



| 15.   | USUPL Mohoba   | 76  |
|-------|--|-----|
| 15.1. | About Project  | 76  |
| 15.2. | Technology   | 77  |
| 15.3. | Project Design   | 79  |
| 15.4. | Power evacuation   | 80  |
| 16.   | TL Kanji   | 81  |
| 16.1. | About Project  | 81  |
| 16.2. | Technology   | 82  |
| 16.3. | Project Design   | 84  |
| 16.4. | Power evacuation   | 85  |
| 17.   | TL Nangla  | 86  |
| 17.1. | About Project  | 86  |
| 17.2. | Technology   | 87  |
| 17.3. | Project Design   | 89  |
| 17.4. | Power evacuation   | 90  |
| 18.   | TL Tinwari   | 90  |
| 18.1. | About Project  | 90  |
| 18.2. | Technology   | 91  |
| 18.3. | Project Design   | 93  |
| 18.4. | Power evacuation   | 94  |
| 19.   | TL Gadna   | 94  |
| 19.1. | About Project  | 94  |
| 19.2. | Technology   | 95  |
| 19.3. | Project Design   | 97  |
| 19.4. | Power evacuation   | 98  |
| 20.   | TL GGEL  | 98  |
| 20.1. | About Project  | 98  |
| 20.2. | Technology   | 99  |
| 20.3. | Project Design   | 100 |
| 20.4. | Power evacuation   | 101 |
| 21.   | Terralight Solar Energy SitamauSS Private Limited (TL SitamauSS) | 101 |



# List of Acronyms

| Acronym  | Meaning   |  |  |  |
|----------|---|--|--|--|
| AC       | Alternate Current                                 |  |  |  |
| ACDB     | AC Distribution Board                             |  |  |  |
| ACSR     | Aluminum Conductor Steel-Reinforced               |  |  |  |
| BNEF     | Bloomberg New Energy Finance                      |  |  |  |
| c-Si     | crystalline Silicon                               |  |  |  |
| COD      | Commercial operation date                         |  |  |  |
| CUF      | Capacity utilization Factor                       |  |  |  |
| DC       | Direct Current                                    |  |  |  |
| GSS      | Grid Substation                                   |  |  |  |
| GWh      | Giga Watt hour                                    |  |  |  |
| HV       | High Voltage                                      |  |  |  |
| IAM      | Incident Angle Modifier                           |  |  |  |
| IE       | Independent Engineer                              |  |  |  |
| IEC      | International Electrotechnical Commission         |  |  |  |
| IEEE     | Institute of Electrical and Electronics Engineers |  |  |  |
| IS       | Indian Standard                                   |  |  |  |
| ISO      | International Organization for Standardization    |  |  |  |
| kV       | kilo Volt   |  |  |  |
| kVA      | kilo Volt Ampere                                  |  |  |  |
| kWh      | kilo Watt hour                                    |  |  |  |
| LID      | Light Induced Degradation                         |  |  |  |
| LV       | Low Voltage                                       |  |  |  |
| kA       | Karnataka   |  |  |  |
| MH       | Maharashtra                                       |  |  |  |
| MMS      | Module Mounting Structure                         |  |  |  |
| MV       | Medium Voltage                                    |  |  |  |
| MVA      | Mega Volt Ampere                                  |  |  |  |
| MW / MWp | Mega Watt / Mega Watt peak                        |  |  |  |
| MWh      | Mega Watt hour                                    |  |  |  |
| OHSAS    | Occupational Health and Safety Assessment Series  |  |  |  |
| PSS      | Pooling Substation                                |  |  |  |
| PV       | Photovoltaic                                      |  |  |  |
| RE       | Renewable Energy                                  |  |  |  |
| SLD      | Single Line Diagram                               |  |  |  |
| SolarGIS | A weather data source                             |  |  |  |
| TDD      | Technical Due Diligence                           |  |  |  |
| VDR      | Virtual Data Room                                 |  |  |  |



# 1. Introduction

TruBoard Credit Monitoring Services Private Limited ('TruBoard') in capacity of Independent Engineer (IE) appointed by India Grid Trust ('the Client) for conducting technical review of a solar portfolio ('the Projects' or 'the Portfolio'). This report summarises the design configuration of each asset in the portfolio based on the review of the documents provided by the Client.

The Portfolio considered in this study comprises ground mounted solar Photovoltaic (PV) and Concentrated Solar Power (CSP) projects of cumulative capacity of 455 MW AC and 538 MWp DC.

In this Portfolio, all the Projects are operational and spread over seven different states of India. The geographical coordinates of the project sites are listed in **Table 1**.

| S. N. | SPV  | Project                            | Location                                 | Coordinates<br>(°N, °E) |
|-------|--|------------------------------------|--|-------------------------|
| 1.    | PLG Photovoltaic Pvt. Ltd.                         | PLG Patan                          | Sami, Patan                              | 23.92, 71.52            |
| 2.    | Terralight Solar Energy Charanka Pvt. Ltd.         | Terralight<br>Charanka             | Charanka                                 | 23.91, 71.21            |
| 3.    | Solar Edge Power and Energy Pvt.<br>Ltd.           | Solar Edge<br>Beed                 | Beed                                     | 18.92, 76.36            |
| 4.    | Solar Edge Power and Energy Pvt.<br>Ltd.           | Solar Edge<br>Jalgaon              | Jalgaon                                  |                         |
| 5.    | Globus Steel and Power Pvt. Ltd.                   | Globus<br>Mandsaur                 | Nataram Village,<br>Sitamau,<br>Mandsaur | 24.08, 75.34            |
| 6.    | Terralight Solar Energy Patlasi Pvt.<br>Ltd.       | Terralight<br>Patlasi              | Village Choti<br>Patlasi, Mandsaur       | 24.04, 75.35            |
| 7.    | Terralight Solar Energy Nangla<br>Pvt. Ltd.        | Terralight<br>Nangla               | Nangla, Talwandi<br>Saboo, Bhatinda      | 29.86, 75.19            |
| 8.    | Terralight Solar Energy Tinwari<br>Private Limited | Terralight<br>Tinwari              | Jodhpur                                  | 26.52, 72.86            |
| 9.    | Terralight Solar Energy Gadna Pvt.<br>Ltd.         | Terralight<br>Gadna                | Gadna, Bap,<br>Jodhpur                   | 27.44, 72.41            |
| 10.   | Universal Saur Urja Pvt. Ltd.                      | USUPL Bap                          | Bap, Jodhpur                             | 27.48, 72.31            |
| 11.   | Universal Saur Urja Pvt. Ltd.                      | USUPL<br>Mahoba                    | Mohoba district                          | 25.31, 79.41            |
| 12.   | Terralight Kanji Solar Pvt. Ltd.                   | Terralight Kanji<br>Lalitpur       | Lalitpur                                 | 24.69, 78.41            |
| 13.   | Terralight Rajapalayam Solar Pvt.<br>Ltd.          | Terralight<br>Rajapalayam          | Rajapalayam                              | 9.33, 77.60             |
| 14.   | Terralight Kanji Solar Pvt. Ltd.                   | Terralight Kanji<br>Tiruvannamalai | Tiruvannamalai                           | 12.35, 78.95            |

#### Table 1 Project location and coordinates



| S. N. | SPV   | Project                  | Location     | Coordinates<br>(°N, °E) |
|-------|---|--------------------------|--------------|-------------------------|
| 15.   | Universal Mine Developers & Service Providers Pvt. Ltd. | UMD Amathur              | Amathur      | 9.55, 77.88             |
| 16.   | Universal Mine Developers & Service Providers Pvt. Ltd. | UMD Kovilpatti           | Kovilpatti   | 9.09, 77.78             |
| 17.   | TN Solar Power Energy Pvt. Ltd.                         | TN Solar<br>Thuthookudi  | Thuthookudi  | 9.12, 78.11             |
| 18.   | TN Solar Power Energy Pvt. Ltd.                         | TN Solar<br>Virudhunagar | Virudhunagar | 9.44, 78.17             |
| 19.   | TN Solar Power Energy Pvt. Ltd.                         | TN Solar<br>Dindigul     | Dindigul     | 10.49, 78.06            |
| 20.   | Godwari Green Energy Ltd.                               | GGEL CSP                 | Nokh         | 27.60, 72.23            |

Table 2 presents details on the project capacity, commercial operation date (COD) and offtaker.

#### Table 2 About Project capacity & COD

| S. N. | SPV        | Project                            | AC       | DC       | COD       | Off-taker |
|-------|------------|------------------------------------|----------|----------|-----------|-----------|
|       |            |                                    | Capacity | Capacity |           |           |
| 1.    | PLG        | PLG Patan                          | 20.00    | 20.00    | 23-Feb-12 | GUVNL     |
| 2.    | TSEC       | Terralight Charanka                | 13.00    | 15.00    | 28-Mar-12 | GUVNL     |
| 3.    | SolarEdge  | Solar Edge Beed                    | 80.00    | 104.00   | 22-Apr-18 | SECI      |
| 4.    |            | Solar Edge Jalgaon                 | 50.00    | 64.94    | 26-Apr-18 | SECI      |
| 5.    | Globus     | Globus Mandsaur                    | 20.00    | 23.60    | 29-Jan-16 | MPPMCL    |
| 6.    | TL Patlasi | Terralight Patlasi                 | 20.00    | 22.10    | 12-Jun-15 | SECI      |
| 7.    | TL Nangla  | Terralight Nangla                  | 4.00     | 4.20     | 24-Mar-15 | PSPCL     |
| 8.    | TSETPL     | Terralight Tinwari                 | 5.00     | 5.84     | 15-Oct-11 | NVVN      |
| 9.    | TL Gadna   | Terralight Gadna                   | 5.00     | 5.50     | 20-Mar-13 | NVVN      |
| 10.   | Jodhpur    | USUPL Bap                          | 20.00    | 25.90    | 26-Mar-13 | NVVN      |
| 11.   | USUPL      | USUPL Mahoba                       | 30.00    | 36.98    | 15-Sep-16 | UPPCL     |
| 12.   | Lalitpur   | Terralight Kanji Lalitpur          | 10.00    | 12.40    | 19-Mar-15 | UPPCL     |
| 13.   | TRSPL      | Terralight Rajapalayam             | 50.00    | 54.00    | 26-Sep-18 | TANGEDCO  |
| 14.   | TKSPL      | Terralight Kanji<br>Tiruvannamalai | 30.00    | 36.01    | 26-Mar-16 | TANGEDCO  |
| 15.   | UMD        | UMD Amathur                        | 12.00    | 14.41    | 16-Nov-16 | TANGEDCO  |
| 16.   |            | UMD Kovilpatti                     | 13.00    | 15.60    | 21-Mar-16 | TANGEDCO  |
| 17.   | TNSEPL     | TN Solar Thuthookudi               | 10.00    | 12.00    | 31-Oct-15 | TANGEDCO  |
| 18.   |            | TN Solar Virudhunagar              | 8.00     | 9.60     | 28-Sep-15 | TANGEDCO  |
| 19.   |            | TN Solar Dindigul                  | 5.00     | 6.00     | 28-Dec-15 | TANGEDCO  |
| 20.   | GGEPL      | Godawari Green<br>Energy Ltd       | 50.00    | 50.00    | 9-Mar-14  | NVVN      |
|       | Total      |                                    | 455.00   | 538.09   |           |           |

TruBoard Partners has undertaken the study covering the agreed scope of works with the Client.



This report is based on documentation provided by the Client via a Virtual Data Room (VDR). The documentation review has been further supported by an ongoing Question and Answer (Q&A) process established between TruBoard and the Client. While every effort has been made to check sources of information, TruBoard takes no responsibility for the completeness or otherwise of the information provided for the purpose of the review.

The tracker in Table 3 shows the status of input data received and desktop review performed for this study.

| Project                   | Project AC<br>SLD | Project DC<br>SLD | PV Module<br>Datasheet | Inverter<br>Datasheet | Transformer<br>Datasheet |
|---------------------------|-------------------|-------------------|------------------------|-----------------------|--------------------------|
| PLG Patan                 | ✓                 | √                 | ✓                      | ×                     | ×                        |
| Terralight Charanka       | ✓                 | √                 | √                      | ×                     | ✓                        |
| Solar Edge Beed           | ×                 | √                 | $\checkmark$           | ×                     | $\checkmark$             |
| Solar Edge Jalgaon        | ×                 | $\checkmark$      | $\checkmark$           | $\checkmark$          | $\checkmark$             |
| Globus Mandsaur           | ✓                 | $\checkmark$      | $\checkmark$           | $\checkmark$          | $\checkmark$             |
| Terralight Patlasi        | $\checkmark$      | $\checkmark$      | $\checkmark$           | $\checkmark$          | ×                        |
| Terralight Nangla         | $\checkmark$      | $\checkmark$      | $\checkmark$           | ×                     | $\checkmark$             |
| Terralight Tinwari        | $\checkmark$      | $\checkmark$      | $\checkmark$           | $\checkmark$          | ×                        |
| Terralight Gadna          |                   | ×                 | $\checkmark$           | $\checkmark$          | ×                        |
| USUPL Bap                 | $\checkmark$      | $\checkmark$      | $\checkmark$           | ×                     | ×                        |
| USUPL Mahoba              |                   |                   |                        |                       | ×                        |
| Terralight Kanji Lalitpur | $\checkmark$      | $\checkmark$      | $\checkmark$           | $\checkmark$          | ×                        |
| Terralight Rajapalayam    | ×                 | $\checkmark$      | $\checkmark$           | $\checkmark$          | $\checkmark$             |
| Terralight Kanji          | ×                 | ×                 | $\checkmark$           | $\checkmark$          | $\checkmark$             |
| Tiruvannamalai            |                   |                   |                        |                       |                          |
| UMD Amathur               | $\checkmark$      | $\checkmark$      | $\checkmark$           | $\checkmark$          | ×                        |
| UMD Kovilpatti            | ×                 | $\checkmark$      | $\checkmark$           | $\checkmark$          | ×                        |
| TN Solar Thuthookudi      | ×                 | $\checkmark$      | ×                      | ×                     | ×                        |
| TN Solar Virudhunagar     | $\checkmark$      | $\checkmark$      | ×                      | ×                     | ×                        |
| TN Solar Dindigul         | $\checkmark$      | $\checkmark$      | ×                      | ×                     | ×                        |
| GGEL                      | ×                 | -                 | -                      | -                     | -                        |

#### Table 3 Summary of site-wise input data available for study



# 2. PLG Patan

## 2.1. About Project

The 20 MW Project is located at Daisar village of Patan district in Gujarat state of India. The Project was constructed by Engineering, Procurement and Construction (EPC) Contractor; Jahmil Infra and operational since 23<sup>rd</sup> February 2012. Currently the O&M contractor is Mitarsh Energy.

The Project is situated 28 km away from Santalpur tehsil and 75 km away from Patan district headquarter. The nearest railway station is at Patan which is around 28 km away from the site. The nearest airport to the project site is at Ahmedabad which is 125 km away. The Project site is well connected.



#### Figure 1: PLG Patan location





#### Figure 2:PLG Patan – Satellite image of project layout

# 2.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project are indicated in Table 4.

#### Table 4: Summary of key components

| Component | Make and Model              | Quantity |
|-----------|-----------------------------|----------|
| Module    | Kyocera - KD240GX-LPB       | 83,352   |
| Inverter  | Hitachi 1000 kW – Solar PCS | 8        |
|           | Delta DelCEN 1000           | 4        |
|           | ABB PVS800-57-0500kW-A      | 16       |
| IDT       | Voltamp 1.25MVA             | 20       |

## 2.2.1. PV module

Table 5 presents the main technical characteristics of the installed PV modules.



| Parameter                   | UoM    | Description  |
|-----------------------------|--------|--|
| Technology                  |        | Polycrystalline  |
| Peak power (Pmax)           | W      | 240  |
| Voltage at Pmax (Vmpp)      | V      | 29.8   |
| Current at Pmax (Impp)      | А      | 8.06   |
| Open Circuit Voltage (Voc)  | V      | 36.9   |
| Short Circuit Current (Isc) | А      | 8.59   |
| Maximum system voltage      | V      | 1000   |
| Temp coefficient of Pmax    | % / °C | -1.10  |
| Module efficiency           | %      | 16   |
| Degradation                 | %      | 0.8%   |
| Certification               | -      | IEC 61215, IEC61730, TUV certified, Safety Class-II, ISO 9001, ISO 14001 |

#### Table 5: Technical characteristics of PV module

#### 2.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over-power output at the end of 25<sup>th</sup> year.

## 2.2.2. Inverter

Table 6 presents the main technical characteristics of the selected model.

#### Table 6: Technical characteristics of inverter

| Parameter                           | Unit | Hitachi                 | Delta       | ABB                    |
|-------------------------------------|------|-------------------------|-------------|------------------------|
| Model                               | -    | 1000<br>kW_Solar<br>PCS | DeICEN 1000 | PVS800-57-0500kW-<br>A |
| Max. efficiency                     | %    | 98.6                    | 98.6        | 98.6                   |
| Max. DC input voltage               | V    | 1000                    | 1000        | 1100                   |
| Max. DC current                     | А    | 2400                    | 1670        | 1145                   |
| MPPT operating voltage range        | V    | 460 to 900              | 610 - 930   | 450 to 825             |
| Number of MPP independent<br>inputs | No.  | 1                       | 1           | 1                      |
| Max. AC output power                | kW   | 1000                    | 1000        | 600                    |
| Max. AC output current              | А    | 2214                    | 1590        | 965                    |
| Nominal AC voltage                  | V    | 300                     | 400         | 300                    |
| Certification (IEC/IEEE/EN)         | -    | IEC 62116,              | IEC61000,   | IEC 62116, IEC         |
|                                     |      | IEC 61727,              | IEC 62109   | 61727, IEC 61683,      |
|                                     |      | IEC 61683,              | IEC 61683   | IEC 60068,             |
|                                     |      | IEC 60068,              | IEC 60068   | IEC 62109.             |
|                                     |      | IEC 62109.              | IEC 60529   |                        |



## 2.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the models as listed in Table 7.

#### Table 7: Inverter warranty

| -                           |          |
|-----------------------------|----------|
| Make                        | Warranty |
| Hitachi 1000 kW – Solar PCS | 5 years  |
| Delta DeICEN 1000           | 5 years  |
| ABB PVS800-57-0500kW-A      | 5 years  |

## 2.2.3. Inverter Duty Transformer

Table 8 presents the key technical characteristics of the selected Voltamp Inverter Duty Transformer (IDT).

#### **Table 8: Technical characteristics of IDT**

| Parameter                  | Unit | Description                 |
|----------------------------|------|-----------------------------|
|                            |      | Description                 |
| Rating                     | kVA  | 1250                        |
| Туре                       |      | ONAN, Oil Immersed, Outdoor |
| Phases                     | No.  | 3                           |
| Frequency                  | Hz   | 50                          |
| Voltage                    | kV   | 0.32-0.32/11 kV             |
| Windings                   | No.  | 3 (1 HV, 2 LV)              |
| Vector Group               |      | Dyn11yn11                   |
| Impedance at principal tap | %    | 4.98                        |

# 2.3. Project Design

## 2.3.1. DC Configuration

The design configuration of the project has been reviewed. The installed DC capacity of the project is 20 MWp which is connected to 28 inverters of 20 MW cumulative capacity. 24 modules form a string and there are total 3,473 such strings. The fixed tilt Module Mounting Structure (MMS) is at 23° tilt angle. The DC to AC ratio for inverters varies from 0.77 to 1.08. Figure 3 and Figure 4 show the actual photographs of PV array area and ICR.





# 2.3.2. AC Configuration

As per the information provided by the Client, there are 28 nos. of inverters and connected to the inverter duty transformer (IDT) of suitable rating which step up the voltage to 11 kV. The output of two transformer feeder then connected to the one RMU panel. There are total such ten RMU panels at site which are connected in ring loop. All RMU panels are equipped with all necessary protection devices. The combination of RMU panels further evacuated to plant end 11 kV indoor switchgear panel. The 11 kV indoor switchgear panel having eight incoming feeders from solar PV plant, one auxiliary transformer feeder and two outgoing cable feeders. The 11 kV switchgear panel equipped with all necessary protection devices, however the details of the protections are not indicated in the SLD. Figure 5 and Figure 6 show the actual photographs of IDT and Inverter.

#### Figure 5: IDT

Figure 6: Inverter




# 2.4. Power evacuation

The output combined power at 11 kV further step to 66 kV via two numbers of 12.5 MVA 11/66 kV power transformer which is located at Pooling Substation (PSS). The step-up power at 66 kV further evacuated to 66 kV GETCO Dahisar Substation via 66 kV overhead transmission line.



## Figure 7: Power Evacuation Schematic



## Figure 8: Plant end Pooling Substation



# 3. Terralight Charanka

# 3.1. About Project

The 15 MW Project is located at Charanka village of Patan district in Gujarat state of India. The Project was constructed by EPC Contractor; M/s. Enfinity Solar Solution Pvt. Ltd and operational since 28<sup>th</sup> March 2012. Currently the O&M contractor is Mitarsh Energy.

The Project is situated 21 km away from Santalpur and 112 km away from Patan district headquarter. The nearest railway station is at Patan which is around 21 km away from the site. The nearest airport to the project site is at Ahmedabad which is 184 km away. The Project site is well connected.



Figure 9: TL Charanka location




Figure 10:TL Charanka – Satellite image of project layout





# 3.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 9.

| Table 9: | Summary | of key | components |
|----------|---------|--------|------------|
|----------|---------|--------|------------|

| Component | Make and Model              | Quantity |
|-----------|-----------------------------|----------|
| Module    | First Solar FS-280          | 187,499  |
| Inverter  | Hitachi 1000 kW – Solar PCS | 7        |
|           | Delta DeICEN 1000           | 6        |
| IDT       | Voltamp 1.25MVA             | 13       |

## 3.2.1. PV module

Table 10 presents the main technical characteristics of the installed PV modules.

#### Table 10: Technical characteristics of PV modules

| Parameter                   | UoM  | Description  |
|-----------------------------|------|--|
| Technology                  |      | Thin film  |
| Peak power (Pmax)           | W    | 80   |
| Voltage at Pmax (Vmpp)      | V    | 71.2   |
| Current at Pmax (Impp)      | A    | 1.12   |
| Open Circuit Voltage (Voc)  | V    | 91.5   |
| Short Circuit Current (Isc) | A    | 1.22   |
| Maximum system voltage      | V    | 1000   |
| Temp coefficient of Pmax    | %/°C | -0.25  |
| Degradation                 | %    | 0.7%   |
| Certification               | -    | IEC 61646, IEC61730, TUV certified, CE Certified, ISO 9001 |

#### 3.2.1.1. PV module warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

## 3.2.2. Inverter

Table 11 presents the main technical characteristics of the selected model.



#### Table 11: Technical characteristics of inverter

| Parameter                        | Unit | Hitachi   | Delta  |
|----------------------------------|------|---|--|
| Model                            | -    | 1000 kW_Solar PCS   | DelCEN 1000  |
| Max. efficiency                  | %    | 98.6  | 98.6   |
| Max. DC input voltage            | V    | 1000  | 1000   |
| Max. DC current                  | А    | 2400  | 1670   |
| MPPT operating voltage range     | V    | 460 - 900   | 610 - 930  |
| Number of MPP independent inputs | No.  | 1   | 1  |
| Max. AC output power             | kW   | 1000  | 1000   |
| Max. AC output current           | A    | 2214  | 1590   |
| Nominal AC voltage               | V    | 300   | 400  |
| Certification (IEC/IEEE/EN)      | -    | IEC 62116, IEC<br>61727, IEC 61683,<br>IEC 60068,<br>IEC 62109. | IEC61000, IEC<br>62109 IEC 61683<br>IEC 60068 IEC<br>60529 |

#### 3.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the models as listed in Table 12.

#### Table 12: Inverter warranty

| Make                      | Warranty |
|---------------------------|----------|
| Hitachi 1000 kW_Solar PCS | 5 years  |
| Delta DeICEN 1000         | 5 years  |

## 3.2.3. Inverter Duty Transformer

Table 13 presents the key technical characteristics of the selected Voltamp IDT.

#### **Table 13: Technical characteristics of IDT**

| Parameter                  | Unit | Description                 |
|----------------------------|------|-----------------------------|
| Rating                     | kVA  | 1250                        |
| Туре                       |      | ONAN, Oil Immersed, Outdoor |
| Phases                     | No.  | 3                           |
| Frequency                  | Hz   | 50                          |
| Voltage                    | kV   | 0.32-0.32/11 kV             |
| Windings                   | No.  | 3 (1 HV, 2 LV)              |
| Vector Group               |      | Dyn11yn11                   |
| Impedance at principal tap | %    | 4.98                        |



# 3.3. Project Design

## 3.3.1. DC Configuration

The design configuration of the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 15 MWp which is connected to 18 inverters of 13 MW cumulative capacity. 9 or 10 modules form a string and there are total 19,549 such strings. The fixed tilt MMS at 22° tilt angle has been considered. The DC to AC ratio for inverters varies from 0.58 to 1.15. Figure 11 and Figure 12 show the actual photographs of PV array area and ICR.

#### Figure 11: Solar PV array

#### Figure 12: ICR



# 3.3.2. AC Configuration

As per the information provided by the Client, there are 13 nos. of inverters of 1000 kW each connected to the inverter duty transformer (IDT) of suitable rating which step up the voltage to 11 kV. The output of two transformer feeder then connected to the one RMU panel. There are total such seven RMU panels at site which are connected in ring loop. All RMU panels are equipped with all necessary protection devices, which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices. The combination of RMU panels further evacuated to plant end 11 kV indoor switchgear panel. There are two nos. of 11 kV indoor switchgear panel. Each switchgear panel have four incoming feeders from solar PV plant, and one outgoing cable feeders. The 11 kV switchgear panel equipped with all necessary protection devices. Each 11 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. has been furnished by the Client.

# 3.4. Power evacuation

The output of each 11 kV switchgear panel further step to 66 kV via one numbers of 12.5 MVA 11/66 kV and 6.3 MVA 11/66 kV power transformer which is located at Pooling Substation (PSS). The step-



up power at 66 kV further evacuated to 400 / 66 kV GETCO Charanka Substation via 66 kV underground cable feeder.

#### Figure 13: Power Evacuation Schematic



# 4. Solar Edge Beed

## 4.1. About Project

The 80 MW (30 MW and 50 MW) Project is located at Mhatargaon village (30 MW) and Bhilegaon village (50 MW) of Beed district in Maharashtra state of India. The Project was constructed by EPC Contractor; M/s. Sterling & Wilson Pvt. Ltd., and operational since 22<sup>nd</sup> April 2018. Currently the O&M contractor is Param.

The Project is situated 21 km away from Dharur tehsil and 72 km away from Beed district headquarter. The nearest railway station is at Parli Vaijnath which is around 17 km away from the site. The nearest airport to the project site is at Nanded Airport which is 90 km away. The Project site is well connected.

#### Figure 14: Solar Edge Beed location







Figure 15:Solar Edge Beed 30 MW – Satellite image of project layout

Figure 16:Solar Edge Beed 50 MW – Satellite image of project layout



# 4.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 14 and Table 15.



| Table 14: Summary of key components for 30 live |                           |          |  |
|---|---------------------------|----------|--|
| Component                                       | Make and Model            | Quantity |  |
| Module  | JA Solar JAM60-S10-325-PR | 120,497  |  |
| Inverter  | ABB PVS980-58-2000kW      | 15       |  |
| IDT1  | Shilchar 2 MVA            | 1        |  |
|   | Shilchar 4 MVA            | 7        |  |

#### Table 14: Summary of key components for 30 MW

#### Table 15: Summary of key components for 50 MW

| Component | Make and Model                  | Quantity |
|-----------|---------------------------------|----------|
| Module    | Canadian solar CS3K-320 MS 1500 | 120,714  |
|           | Astroenergy CHSM6612P-325W      | 79,980   |
| Inverter  | ABB PVS980-58-2000kW            | 25       |
| IDT       | Shilchar 2 MVA                  | 1        |
|           | Shilchar 4 MVA                  | 12       |

## 4.2.1. PV modules

Table 16 presents the main technical characteristics of the installed PV modules.

| Parameter                     | UoM  | JA Solar  | JA Solar  | Canadian<br>solar   | Astroenergy  |
|-------------------------------|------|---|---|---|--|
| Technology                    |      | Polycrystalline   | Polycrystalline   | Polycrystalline   | Polycrystalline  |
| Peak power (Pmax)             | W    | 320   | 325   | 320   | 325  |
| Voltage at Pmax<br>(Vmpp)     | V    | 37.28   | 37.39   | 36.8  | 37.26  |
| Current at Pmax<br>(Impp)     | A    | 9.09  | 9.17  | 8.69  | 9.00   |
| Open Circuit Voltage<br>(Voc) | V    | 46.12   | 46.38   | 45.3  | 45.98  |
| Short Circuit Current (Isc)   | A    | 8.58  | 8.69  | 9.26  | 9.57   |
| Maximum system voltage        | V    | 1500  | 1500  | 1000  | 1000 or 1500   |
| Temp coefficient of<br>Pmax   | %/°C | -0.41   | -0.41   | -0.41   | -0.40  |
| Module efficiency             | %    | 16.5  | 16.7  | 16.46   | 17.2   |
| Degradation                   | %    | 0.7%  | 0.7%  | 0.7%  | 0.7%   |
| Certification                 | -    | IEC 61215,<br>IEC 61730,<br>CE Certified,<br>ISO 9001,<br>ISO 14001 | IEC 61215,<br>IEC 61730,<br>CE Certified,<br>ISO 9001,<br>ISO 14001 | IEC 61215,<br>IEC 61730,<br>IEC 61701,<br>IEC 62716<br>CE Certified | IEC 61215,<br>IEC 61730,<br>CE Certified,<br>TUV Nord<br>Certified |

#### Table 16: Technical characteristics of PV modules

## 4.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application,



installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

## 4.2.2. Inverter

Table 17 presents the main technical characteristics of the selected model.

| Parameter                        | Unit | Description  |
|----------------------------------|------|--|
| Model                            | -    | PVS980-58-2000kW                                       |
| Max. efficiency                  | %    | 98.8   |
| Max. DC input voltage            | V    | 1500   |
| Max. DC current                  | A    | 2400   |
| MPPT operating voltage range     | V    | 935 to 1100  |
| Number of MPP independent inputs | No.  | 1  |
| Max. AC output power             | kW   | 2000   |
| Max. AC output current           | А    | 1750   |
| Nominal AC voltage               | V    | 660  |
| Certification (IEC/IEEE/EN)      | -    | IEC 62116, IEC 61727, IEC 61683, IEC 60068, IEC 62109. |

#### Table 17: Technical characteristics of inverter

#### 4.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the model listed in Table 18.

| Make                 | Warranty |
|----------------------|----------|
| ABB PVS980-58-2000kW | 5 years  |
|                      |          |

## 4.2.3. Inverter Duty Transformer

Table 19 presents the key technical characteristics of the selected Shilchar IDT.

#### Table 19: Technical characteristics of IDT

| Parameter                  | Unit | Shilchar (2 MVA)            | Shilchar (4 MVA)            |
|----------------------------|------|-----------------------------|-----------------------------|
| Rating                     | kVA  | 2000                        | 4000                        |
| Туре                       |      | ONAN, Oil Immersed, Outdoor | ONAN, Oil Immersed, Outdoor |
| Phases                     | No.  | 3                           | 3                           |
| Frequency                  | Hz   | 50                          | 50                          |
| Voltage                    | kV   | 0.66/33kV                   | 0.66-0.66/33 kV             |
| Windings                   | No.  | 2 (1 HV, 1 LV)              | 3 (1 HV, 2 LV)              |
| Vector Group               |      | Dy11                        | Dy11y11                     |
| Impedance at principal tap | %    | 6.25                        | 7.15                        |



# 4.3. Project Design

# 4.3.1. DC Configuration

The design configuration for 30 MW project has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 39.4 MWp which is connected to 15 inverters of 30 MW cumulative capacity. 31 modules form a string and there are total 3,887 such strings. The fixed tilt Module Mounting Structure at 16° tilt angle has been considered. The DC to AC ratio for inverters are 1.32.

The design configuration for 50 MW project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 64.6 MWp which is connected to 25 inverters of 50 MW cumulative capacity. 31 modules form a string and there are total 6.474 such strings. The fixed tilt Module Mounting Structure at 16° tilt angle has been considered. The DC to AC ratio for inverters are 1.3. Figure 17 show the actual photographs of PV array area.

# Figure 17: Solar PV Array



# 4.3.2. AC Configuration

As per the submitted SLD for 30 MW there are 15 nos. of inverters, in which 14 are connected to the 7 nos. of three winding inverter duty transformer (IDT) of 4000 kVA, 0.66/0.66/33 kV rating and one inverter is connected to two winding IDT of 2000 kVA, 0.66/33 kV rating. The output of IDT further connected to 33kV outdoor VCB panel. The 33 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices has been furnished by the Client. The output of the such 8 nos. of 33 kV switchgear panels are further connected to one no. of 33 kV indoor HT switchgear panel via cable feeders at MCR building. The 33 kV switchgear panel has 8 incoming feeders from solar PV plant, one bus coupler and two outgoing cable feeders/ 33kV transmission line via double pole structure arrangement to another 50 MW solar PV plant. The 33 kV indoor HT switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions




along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices has been furnished by the Client.

As per the submitted documents there are 25 nos. of inverters, in which 24 are connected to the 12 nos. of three winding inverter duty transformer (IDT) of 4000 kVA, 0.66/0.66/33 kV rating and one inverter is connected to two winding IDT of 2000 kVA, 0.66/33 kV rating. The output of IDT further connected to 33kV outdoor SF6 VCB panel / 33 kV ICOG panel. The 33 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices has been furnished by the Client. The output of the such 13 nos. of 33 kV switchgear panels are further connected to one no. of 33 kV indoor HT switchgear panel via cable feeders at MCR building. The 33 kV switchgear panel has 13 incoming feeders from solar PV plant, one bus coupler, one cable feeder of 30 MW solar PV plant and two outgoing cable feeders. The 33 kV indoor HT switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices has been furnished by the Client.

# 4.4. Power evacuation

The output of 33 kV switchgear panel further step to 132 kV via two numbers of 50/55 MVA 132/33 kV power transformer which is located at 50 MW solar PV plant end. The step-up power at 132 kV further evacuated to Pangri Grid Substation via 132 kV Transmission line.








# 5. Solar Edge Jalgaon

## 5.1. About Project

The 50 MW Project is located at Mauje Wadhave village of Jalgaon district in Maharashtra state of India. The Project was constructed by EPC Contractor; M/s. Sterling & Wilson Pvt. Ltd., and operational since 26<sup>th</sup> April 2018. Currently the O&M contractor is Param.

The Project is situated 25 km away from Muktainagar tehsil and 70 km away from Jalgaon district headquarter. The nearest railway station is at Bhusawal railway which is around 25 km away from the site. The nearest airport to the project site is at Aurangabad Airport which is 180 km away. The Project site is well connected.



#### Figure 19: Solar Edge Jalgaon location





#### Figure 20:Solar Edge Jalgaon 50 MW – Satellite image of project layout

# 5.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 20.

| Component | Make and Model                     | Quantity |
|-----------|------------------------------------|----------|
| Module    | Canadian solar CS3K-320 MS<br>1500 | 56,699   |
|           | Astroenergy CHSM6612P-320W         | 121,830  |
|           | JA Solar JAM60-S10-325-PR          | 7,874    |
|           | JA Solar JAM60-S09-330-PR          | 16,027   |
| Inverter  | ABB PVS980-58-2000kW               | 25       |
| IDT       | Shilchar 2 MVA                     | 1        |
|           | Shilchar 4 MVA                     | 12       |

#### Table 20: Summary of key components

## 5.2.1. PV module

Table 21 presents the main technical characteristics of the installed PV modules.



| Parameter                      | UoM  | JA Solar  | JA Solar  | Canadian<br>solar   | Astroenergy  |
|--------------------------------|------|---|---|---|--|
| Technology                     |      | Polycrystalline   | Polycrystalline   | Polycrystalline   | Polycrystalline  |
| Peak power (Pmax)              | W    | 330   | 325   | 320   | 320  |
| Voltage at Pmax<br>(Vmpp)      | V    | 37.65   | 37.39   | 36.8  | 37.02  |
| Current at Pmax (Impp)         | А    | 9.28  | 9.17  | 8.69  | 8.65   |
| Open Circuit Voltage<br>(Voc)  | V    | 46.40   | 46.38   | 45.3  | 45.45  |
| Short Circuit Current<br>(Isc) | A    | 8.77  | 8.69  | 9.26  | 9.25   |
| Maximum system voltage         | V    | 1500  | 1500  | 1000  | 1000 or 1500   |
| Temp coefficient of<br>Pmax    | %/°C | -0.41   | -0.41   | -0.41   | -0.40  |
| Module efficiency              | %    | 17  | 16.7  | 16.46   | 16.5   |
| Degradation                    | %    | 0.7%  | 0.7%  | 0.7%  | 0.7%   |
| Certification                  | -    | IEC 61215,<br>IEC 61730,<br>CE Certified,<br>ISO 9001,<br>ISO 14001 | IEC 61215,<br>IEC 61730,<br>CE Certified,<br>ISO 9001,<br>ISO 14001 | IEC 61215,<br>IEC 61730,<br>IEC 61701,<br>IEC 62716<br>CE Certified | IEC 61215,<br>IEC 61730,<br>CE Certified,<br>TUV Nord<br>Certified |

#### Table 21: Technical characteristics of PV modules

#### 5.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

## 5.2.2. Inverter

Table 22 presents the main technical characteristics of the selected model.

#### Table 22: Technical characteristics of Inverter

| Parameter                        | Unit | Description      |
|----------------------------------|------|------------------|
| Model                            | -    | PVS980-58-2000kW |
| Max. efficiency                  | %    | 98.8             |
| Max. DC input voltage            | V    | 1500             |
| Max. DC current                  | А    | 2400             |
| MPPT operating voltage range     | V    | 935 to 1100      |
| Number of MPP independent inputs | No.  | 1                |
| Max. AC output power             | kW   | 2000             |



| Parameter                   | Unit | Description   |
|-----------------------------|------|---|
| Max. AC output current      | А    | 1750  |
| Nominal AC voltage          | V    | 660   |
| Certification (IEC/IEEE/EN) | -    | IEC 62116, IEC 61727, IEC 61683, IEC 60068,<br>IEC 62109. |

## 5.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the model listed in Table 23.

#### Table 23: Inverter warranty

| Make                 | Warranty |
|----------------------|----------|
| ABB PVS980-58-2000kW | 5 years  |

# 5.2.3. Inverter Duty Transformer

Table 24 presents the key technical characteristics of the selected Shilchar transformer.

#### Table 24: Technical characteristics of IDT

| Parameter                  | Unit | Shilchar (2 MVA)               | Shilchar (4 MVA)               |
|----------------------------|------|--------------------------------|--------------------------------|
| Rating                     | kVA  | 2000                           | 4000                           |
| Туре                       |      | ONAN, Oil<br>Immersed, Outdoor | ONAN, Oil<br>Immersed, Outdoor |
| Phases                     | No.  | 3                              | 3                              |
| Frequency                  | Hz   | 50                             | 50                             |
| Voltage                    | kV   | 0.66/33kV                      | 0.66-0.66/33 kV                |
| Windings                   | No.  | 2 (1 HV, 1 LV)                 | 3 (1 HV, 2 LV)                 |
| Vector Group               |      | Dy11                           | Dy11y11                        |
| Impedance at principal tap | %    | 6.25                           | 7.15                           |

# 5.3. Project Design

## 5.3.1. DC Configuration

The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 64.9 MWp which is connected to 25 inverters of 50 MW cumulative capacity. 31 modules form a string and there are total 6,530 such strings. The fixed tilt Module Mounting Structure at 16° tilt angle has been considered. The DC to AC ratio for inverters are 1.3. Figure 21 shows the actual photographs of PV array area.



Figure 21:Solar PV Array



# 5.3.2. AC Configuration


As per the submitted documents for there are 25 nos. of inverters, in which 24 are connected to the 12 nos. of three winding inverter duty transformer (IDT) of 4000 kVA, 0.66/0.66/33 kV rating and one inverter is connected to two winding IDT of 2000 kVA, 0.66/33 kV rating. The output of IDT further connected to 33kV indoor switchgear panel. There are six no of 1-in-1 out 33kV switchgear panel present which have one incoming transformer feeder and one outgoing cable feeder in the 33 kV indoor switchgear panel. There are six no of 2-in-1 out 33kV switchgear panel present which have one incoming of 1-in-1 out 33kV switchgear panel present which have one incoming of 1-in-1 out 33kV switchgear panel feeder, one auxiliary transformer feeder and one outgoing cable feeder. The output of such five 2-in-1 out 33 kV switchgear panel further evacuate the power via cable feeder and the balance one evacuate the power via 33 kV overhead line via double pole structure. The 33 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices has been furnished by the Client.

# 5.4. Power evacuation

The output of 33 kV switchgear panel further step to 132 kV via two numbers of 25 MVA132/33 kV power transformer which is located at 50 MW solar PV plant end. The step-up power at 132 kV further evacuated to Muktainagar Grid Substation via 132 kV overhead Transmission line.



#### Figure 22: Power Evacuation Schematic



# 6. Globus Mandsaur

## 6.1. About Project

The Project is located at Nataram village of Mandasaur District in Madhya Pradesh state of India. The Project was constructed by EPC Contractor; M/s. Belectric, and operational since 29<sup>th</sup> Jan 2016. Currently the O&M contractor is Mitarsh energy.

The Project is situated 40 km away from Mandasaur district headquarters. The nearest railway station is at Mandsor railway which is around 32 km away from the site. The nearest airport to the project site is at Indore Airport which is 200 km away. The Project site is well connected.






Figure 23: Globus location

Figure 24: Globus 20 MW – Satellite image of project layout





# 6.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 25.

| Component | Make and Model              | Quantity |
|-----------|-----------------------------|----------|
| Module    | Solar Frontier KK SF 165-S  | 143,400  |
| Inverter  | ABB PVS800-57-1000kW        | 1        |
|           | SMA Sunny Central 1000CP XT | 17       |
| IDT       | Shilchar 2.2 MVA            | 9        |

#### Table 25: Summary of key components

## 6.2.1. PV modules

Table 26 presents the main technical characteristics of the installed PV modules.

| Table 26: Technical characteristics of PV modules |      |   |  |  |
|---|------|---|--|--|
| Parameter   | UoM  | Solar Frontier  |  |  |
| Technology  |      | Thinfilm  |  |  |
| Peak power (Pmax)                                 | W    | 165   |  |  |
| Voltage at Pmax (Vmpp)                            | V    | 85.5  |  |  |
| Current at Pmax (Impp)                            | А    | 1.93  |  |  |
| Open Circuit Voltage (Voc)                        | V    | 110   |  |  |
| Short Circuit Current (Isc)                       | А    | 2.20  |  |  |
| Maximum system voltage                            | V    | 1000  |  |  |
| Temp coefficient of Pmax                          | %/°C | -0.31   |  |  |
| Degradation                                       | %    | 0.8%  |  |  |
| Certification                                     | -    | IEC 61646, IEC 61730,<br>CE Certified, ISO 9001,<br>ISO 14001 |  |  |

#### Table 26: Technical characteristics of PV modules

#### 6.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

## 6.2.2. Inverter

Table 27 presents the main technical characteristics of the selected model.

| Parameter       | Unit | ABB              | SMA                        |  |  |
|-----------------|------|------------------|----------------------------|--|--|
| Model           | -    | PVS800-57-1000kW | Sunny Central 1000CP<br>XT |  |  |
| Max. efficiency | %    | 98.8             | 98.7                       |  |  |

#### Table 27: Technical characteristics of Inverter



| Parameter                        | Unit | ABB  | SMA  |  |
|----------------------------------|------|--|--|--|
| Max. DC input voltage            | V    | 1,100  | 1,000  |  |
| Max. DC current                  | А    | 1,710  | 1,635  |  |
| MPPT operating voltage range     | V    | -  | 625 to 850   |  |
| Number of MPP independent inputs | no.  | 1  | 1  |  |
| Max. AC output power             | kW   | 1000   | 1,100  |  |
| Max. AC output current           | А    | 1445   | 1,568  |  |
| Nominal AC voltage               | V    | 405  | 405  |  |
| Certification (IEC/IEEE/EN)      | -    | IEC 62116, IEC 61727,<br>IEC 61683, IEC 60068,<br>IEC 62109. | EN 61000,<br>EMC- Conformity,<br>CE Certified, IEEE 1547 |  |

#### 6.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the model listed in Table 28.

#### Table 28: Inverter warranty

| Make                        | Warranty |
|-----------------------------|----------|
| ABB PVS800-57-1000kW        | 5 years  |
| SMA Sunny Central 1000CP XT | 5 years  |

## 6.2.3. Inverter Duty Transformer

Table 29 presents the key technical characteristics of the selected Shilchar transformer.

| Parameter                  | Unit | Description                 |  |  |
|----------------------------|------|-----------------------------|--|--|
| Rating                     | kVA  | 2200                        |  |  |
| Туре                       |      | ONAN, Oil Immersed, Outdoor |  |  |
| Phases                     | No.  | 3                           |  |  |
| Frequency                  | Hz   | 50                          |  |  |
| Voltage                    | kV   | 0.405/0.405/33kV            |  |  |
| Windings                   | No.  | 3 (1 HV, 2 LV)              |  |  |
| Vector Group               |      | Dy11y11                     |  |  |
| Impedance at principal tap | %    | 6                           |  |  |

# 6.3. Project Design

# 6.3.1. DC Configuration

The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 23.7 MWp which is connected to 18 inverters of 18 MW cumulative capacity. 8 modules form a string and there are total 17,930 such strings. The



fixed tilt Module Mounting Structure at 15° tilt angle has been considered. The DC to AC ratio for inverters are 1.3. Figure 25 and Figure 26 show the actual photographs of PV array area and ICR.



# 6.3.2. AC Configuration

As per the submitted SLD for there are 18 nos. of inverters which are connected to the 9 nos. of three winding IDT of 2200 kVA, 0.45/0.45/33 kV rating. The output of IDT further connected to the 1-in-1 out 33kV indoor switchgear panel. There are such nine no of 36 kV indoor switchgear panels. All 33 kV indoor switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices. The output of 1-in-1 out switchgear panel further connected to 36 kV Air Insulated Collector substations. There are two nos. of collector substations. The collector substation-2 has four no. of incoming cable feeders from 36 kV indoor switchgear panels, one auxiliary transformer feeder and one outgoing feeder which will further connected to collector substation-1.

The collector substation-1 has five no of incoming cable feeders from 36 kV indoor switchgear panels, one no. of incoming cable feeder from collector substation-2, one auxiliary transformer feeder and one outgoing feeder. Both, 36 kV outdoor collector substation are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. has been furnished by the Client.

# 6.4. Power evacuation

The outgoing cable feeder of 33 kV collector substation-1 further converted to overhead transmission line with the help of pole structure. The generated combined power at 33 kV further evacuated to Focal Energy Three India Private Limited of 60 MW 132/33 kV pooling substation at Sitamau via 33 kV cable feeder. The transmission line length is of around 6 km.

At PSS the overhead transmission line further converted to cable feeder with the help of double pole structure. Further the cable will connect to the existing 33 kV switchgear panel along with all metering



and protection arrangements. The collected power at 33 kV further step up to 132 kV via three nos. of 20/25 MVA 132/33 kV power transformer at PSS. The step up further evacuated to MPPTCL GSS via single circuit 132 kV transmission line.

### Figure 27: Power Evacuation Schematic



## 7. Terralight Patlasi

### 7.1. About Project

The Project is located at Mandasaur District in Madhya Pradesh state of India. The Project was constructed by EPC Contractor; M/s. Belectric, and operational since 12<sup>th</sup> Jun 2015. Currently the O&M contractor is Mitarsh energy.

The Project is situated 32 km away from Mandasaur district headquarters. The nearest railway station is at Mandsor railway which is around 35 km away from the site. The nearest airport to the project site is at Indore Airport which is 196 km away. The Project site is well connected.




Figure 28: TL Patlasi





### Figure 29:TL Patlasi 20 MW – Satellite image of project layout

## 7.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 30.

| Component | Make and Model                 | Quantity |  |  |
|-----------|--------------------------------|----------|--|--|
| Module    | First Solar FS-395             | 233,376  |  |  |
| Inverter  | ABB PVS800-57-1000kW           | 1        |  |  |
|           | SMA Sunny Tripower 20000 TL-30 | 8        |  |  |
|           | SMA Sunny Central 900CP XT     | 19       |  |  |
| IDT       | Shilchar 2.0 MVA               | 10       |  |  |

#### Table 30: Summary of key components

## 7.2.1. PV modules

Table 31 presents the main technical characteristics of the installed PV modules.

| Table 31: Technical characteristics of PV modules |     |             |  |  |
|---|-----|-------------|--|--|
| Parameter   | UoM | First Solar |  |  |
| Technology  |     | Thinfilm    |  |  |
| Peak power (Pmax)                                 | W   | 95          |  |  |
| Voltage at Pmax (Vmpp)                            | V   | 45.8        |  |  |
| Current at Pmax (Impp)                            | А   | 2.08        |  |  |



| Parameter                   | UoM  | First Solar  |
|-----------------------------|------|--|
| Open Circuit Voltage (Voc)  | V    | 58.0   |
| Short Circuit Current (Isc) | А    | 2.29   |
| Maximum system voltage      | V    | 1000   |
| Temp coefficient of Pmax    | %/°C | -0.29  |
| Degradation                 | %    | 0.7%   |
| Certification               | -    | IEC 61646, IEC61730,<br>TUV certified, CE<br>Certified, ISO 9001 |

### 7.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

### 7.2.2. Inverter

Table 32 presents the main technical characteristics of the selected model.

| Parameter                           | Unit | ABB  | SMA  | SMA  |
|-------------------------------------|------|--|--|--|
| Model                               | -    | PVS800-57-<br>1000kW   | Sunny Central<br>900CP XT                                      | Sunny Tripower<br>20000 TL-30                                  |
| Max. efficiency                     | %    | 98.8   | 98.6   | 98.4   |
| Max. DC input voltage               | V    | 1,100  | 1,000  | 1,000  |
| Max. DC current                     | А    | 1,710  | 1,400  | 33   |
| MPPT operating voltage<br>range     | V    | -  | 656 to 850   | 320 to 800   |
| Number of MPP<br>independent inputs | no.  | 1  | 1  | 1  |
| Max. AC output power                | kW   | 1000   | 900  | 20   |
| Max. AC output current              | А    | 1445   | 1411   | 29   |
| Nominal AC voltage                  | V    | 405  | 405  | 405  |
| Certification<br>(IEC/IEEE/EN)      | -    | IEC 62116, IEC<br>61727, IEC<br>61683, IEC<br>60068,<br>IEC 62109. | EN 61000,<br>EMC-<br>Conformity,<br>CE Certified,<br>IEEE 1547 | EN 61000,<br>EMC-<br>Conformity,<br>CE Certified,<br>IEEE 1547 |

#### Table 32: Technical characteristics of Inverter

### 7.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the models listed in Table 33.



#### Table 33: Inverter warranty

| Make                           | Warranty |
|--------------------------------|----------|
| ABB PVS800-57-1000kW           | 5 years  |
| SMA Sunny Central 900CP XT     | 5 years  |
| SMA Sunny Tripower 20000 TL-30 | 5 years  |

### 7.2.3. Inverter Duty Transformer

Table 34 presents the key technical characteristics of the selected Shilchar IDT.

#### Table 34: Technical characteristics of IDT

| Parameter                  | Unit | Shilchar                    |
|----------------------------|------|-----------------------------|
| Rating                     | kVA  | 2000                        |
| Туре                       |      | ONAN, Oil Immersed, Outdoor |
| Phases                     | No.  | 3                           |
| Frequency                  | Hz   | 50                          |
| Voltage                    | kV   | 0.405/0.405/33kV            |
| Windings                   | No.  | 3 (1 HV, 2 LV)              |
| Vector Group               |      | Dy11y11                     |
| Impedance at principal tap | %    | 6                           |

## 7.3. Project Design

### 7.3.1. DC Configuration

The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 22.2 MWp which is connected to 28 inverters of 18 MW cumulative capacity. 16 modules form a string and there are a total of 14,586 such strings. The fixed tilt Module Mounting Structure at 15° tilt angle has been considered. The DC to AC ratio for inverters are 1.3. Figure 30 show the actual photographs of PV array area.

#### Figure 30:Solar PV Array



July 2023



## 7.3.2. AC Configuration

As per the information provided by the Client, there are 28 nos. of inverters and are connected to the inverter duty transformer (IDT) of suitable rating which step up the voltage to 33 kV. The output of IDT further connected to the 1-in-1 out 33kV outdoor air insulated Vacuum Circuit Breaker (VCB) panel. There are such ten nos of 33 kV outdoor air insulated VCB panels. All 33 kV VCB panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices. The output of 1-in-1 out switchgear panel further connected to 33 kV Air Insulated Collector substations. There are two nos. of collector substations. The collector substation-1 has five no. of incoming cable feeders from 33 kV VCB panels, one auxiliary transformer feeder and one outgoing feeder which will further connected to collector substation-2.

The collector substation-2 has five no of incoming cable feeders from 33 kV VCB panels, one no. of incoming cable feeder from collector substation-1, one auxiliary transformer feeder and one outgoing feeder. Both, 36 kV outdoor collector substation are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. has been furnished by the Client.

## 7.4. Power evacuation

The outgoing cable feeder of 33 kV collector substation-1 further converted to overhead transmission line with the help of pole structure. The generated combined power at 33 kV further evacuated to Focal Energy Three India Private Limited of 60 MW 132/33 kV pooling substation at Sitamau via 33 kV double circuit transmission line. The transmission line length is of around 6 km.

At PSS the overhead transmission line further converted to cable feeder with the help of double pole structure. Further the cable will connect to the existing 33 kV switchgear panel along with all metering and protection arrangements. The collected power at 33 kV further step up to 132 kV via three nos. of 20/25 MVA 132/33 kV power transformer at PSS. The step up further evacuated to MPPTCL GSS via single circuit 132 kV transmission line.

### Figure 31: Power Evacuation Schematic





Figure 32: Power transformer



## 8. Terralight Rajapalayam

## 8.1. About Project

The Project is located at Unjampatti Village, Rajapalayam Block, Virudhunagar District Tamilnadu state of India. The Project was constructed by EPC Contractor; M/s. M/s. Sterling & Wilson Pvt. Ltd, and operational since 26<sup>th</sup> Sep 2018. Currently the O&M contractor is AVI Solar Energy.

The Project is situated 72 km away from Virudhunagar district headquarters. The nearest railway station is at Virudhunagar railway which is around 75 km away from the site. The nearest airport to the project site is at Madurai Airport which is 125 km away. The Project site is well connected.







Figure 34:TL Rajapalayam 50 MW – Satellite image of project layout





## 8.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 35.

| Component | Make and Model            | Quantity |
|-----------|---------------------------|----------|
| Module    | JA solar JAM60-S01-325-SC | 83,040   |
|           | JA solar JAM60-S01-330-SC | 81,900   |
| Inverter  | Sineg EP-1250-HA          | 40       |
| IDT       | Shilchar 5 MVA            | 10       |

#### Table 35: Summary of key components

### 8.2.1. PV modules

Table 36 presents the main technical characteristics of the installed PV modules.

| Table 30. Technical characteristics of FV modules |      |                 |                 |  |  |
|---|------|-----------------|-----------------|--|--|
| Parameter   | UoM  | JA Solar        | JA Solar        |  |  |
| Technology  |      | Polycrystalline | Polycrystalline |  |  |
| Peak power (Pmax)                                 | W    | 330             | 325             |  |  |
| Voltage at Pmax (Vmpp)                            | V    | 37.65           | 37.39           |  |  |
| Current at Pmax (Impp)                            | А    | 9.28            | 9.17            |  |  |
| Open Circuit Voltage<br>(Voc)                     | V    | 46.40           | 46.38           |  |  |
| Short Circuit Current (Isc)                       | А    | 8.77            | 8.69            |  |  |
| Maximum system voltage                            | V    | 1500            | 1500            |  |  |
| Temp coefficient of Pmax                          | %/°C | -0.41           | -0.41           |  |  |
| Module efficiency                                 | %    | 17              | 16.7            |  |  |
| Degradation                                       | %    | 0.7%            | 0.7%            |  |  |
| Certification                                     | -    | IEC 61215,      | IEC 61215,      |  |  |
|   |      | IEC 61730,      | IEC 61730,      |  |  |
|   |      | CE Certified,   | CE Certified,   |  |  |
|   |      | ISO 9001,       | ISO 9001,       |  |  |
|   |      | ISO 14001       | ISO 14001       |  |  |

#### Table 36: Technical characteristics of PV modules

### 8.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

### 8.2.2. Inverter

Table 37 presents the main technical characteristics of the selected model.



| Parameter                           | Unit | Description  |
|-------------------------------------|------|--|
| Model                               | -    | EP-1250-HA   |
| Max. efficiency                     | %    |  |
| Max. DC input voltage               | V    | 1,500  |
| Max. DC current                     | А    | 1.754  |
| MPPT operating voltage<br>range     | V    | 800 to 1300  |
| Number of MPP<br>independent inputs | no.  | 1  |
| Max. AC output power                | kW   | 1250   |
| Max. AC output current              | А    | 1.443  |
| Nominal AC voltage                  | V    | 550  |
| Certification<br>(IEC/IEEE/EN)      | -    | IEC/EN 62109-1, IEC/EN 62109-<br>2, EN 61000-6-2, EN 61000-6-3,<br>EN 61000-3-2. |

### Table 37: Technical characteristics of Inverter

### 8.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the model listed in Table 38

#### Table 38: Inverter warranty

| Make             | Warranty |
|------------------|----------|
| Sineg EP-1250-HA | 5 years  |

### 8.2.3. Inverter Duty Transformer

Table 39 presents the key technical characteristics of the selected Shilchar transformer.

|                            | -    |                             |
|----------------------------|------|-----------------------------|
| Parameter                  | Unit | Description                 |
| Rating                     | kVA  | 5000                        |
| Туре                       |      | ONAN, Oil Immersed, Outdoor |
| Phases                     | No.  | 3                           |
| Frequency                  | Hz   | 50                          |
| Voltage                    | kV   | 0.55/0.55/11kV              |
| Windings                   | No.  | 3 (1 HV, 2 LV)              |
| Vector Group               |      | Yd11yd11                    |
| Impedance at principal tap | %    | 6                           |

#### Table 39: Technical characteristics of IDT

## 8.3. Project Design

### 8.3.1. DC Configuration

The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 54 MWp which is connected to 40 inverters



of 50 MW cumulative capacity. 30 modules form a string and there are a total of 5,498 such strings. The fixed tilt Module Mounting Structure at 8° tilt angle has been considered. The DC to AC ratio for inverters are 1.08.


## 8.3.2. AC Configuration

As per the submitted SLD for there are 40 nos. of inverters which are connected to the 10 nos. of three winding IDT of 5 MVA, 0.55/0.55/11 kV rating. The output of IDT further connected to the 1-in-1 out 11 kV switchgear panel. There are such ten nos of 11 kV outdoor switchgear panels. All 11 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices. The output of 1-in-1 out switchgear panel further connected to main HT panel at MCR building. The MCR 11 kV HT panel has ten no. of incoming cable feeders from 11 kV switchgear panel are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection devices feeders for 11 kV switchgear panel are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. has been furnished by the Client.

## 8.4. Power evacuation

The combined generated 50 MW power at 11 kV further step up to 110 kV via two nos. of 24/40 MVA, 110/11 kV power transformer. The elevated power 110 kV further evacuated to Grid Sub Station (GSS) via 110 kV Single Circuit (S/C) transmission line. The 110 kV transmission line is approx. 10 km away from the plant end substation.

### Figure 35: Power Evacuation Schematic




## 9. Terralight Kanji

## 9.1. About Project

The Project is located at Alllyandhi village, Chengam, Tiruvannamalai, District Tamilnadu of India. The Project was constructed by EPC Contractor; M/s. M/s. Sterling & Wilson Pvt. Ltd, and operational since 26<sup>th</sup> March 2016. Currently the O&M contractor is AVI Solar Energy.



The Project is situated 22 km away from Tiruvannamalai district headquarters. The nearest railway station is at Tiruvannamalai railway which is around 25 km away from the site. The nearest airport to the project site is at Puducherry Airport which is 140 km away. The Project site is well connected.



### Figure 36: TL Kanji





### Figure 37:TL Kanji 30 MW – Satellite image of project layout

## 9.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 40.

#### Table 40: Summary of key components

| Component | Make and Model       | Quantity |
|-----------|----------------------|----------|
| Module    | Talesun TD672P-310   | 116,172  |
| Inverter  | ABB PVS800-57-1000kW | 30       |
| IDT       | Shilchar 2.2 MVA     | 14       |
|           | Shilchar 1.1 MVA     | 2        |

### 9.2.1. PV modules

Table 41 presents the main technical characteristics of the installed PV modules.

### Table 41: Technical characteristics of PV module

| Parameter              | UoM | Description     |
|------------------------|-----|-----------------|
| Technology             |     | Polycrystalline |
| Peak power (Pmax)      | W   | 310             |
| Voltage at Pmax (Vmpp) | V   | 36.5            |



| Parameter                   | UoM  | Description   |
|-----------------------------|------|---|
| Current at Pmax (Impp)      | А    | 8.5   |
| Open Circuit Voltage (Voc)  | V    | 45  |
| Short Circuit Current (Isc) | А    | 9.06  |
| Maximum system voltage      | V    | 1000  |
| Temp coefficient of Pmax    | %/°C | -0.4  |
| Module efficiency           | %    | 16  |
| Degradation                 | %    | 0.7%  |
| Certification               | -    | IEC 61215, IEC<br>61730, IEC 61701,<br>IEC 62716, IEC 60068 |

### 9.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

### 9.2.2. Inverter

Table 42 presents the main technical characteristics of the selected model.

 Table 42: Technical characteristics of Inverter

| Parameter                           | Unit | Description  |
|-------------------------------------|------|--|
| Model                               | -    | PVS800-57-1000kW                                       |
| Max. efficiency                     | %    | 98.8   |
| Max. DC input voltage               | V    | 1,100  |
| Max. DC current                     | A    | 1,710  |
| MPPT operating voltage range        | V    | -  |
| Number of MPP independent<br>inputs | no.  | 1  |
| Max. AC output power                | kW   | 1000   |
| Max. AC output current              | А    | 1445   |
| Nominal AC voltage                  | V    | 405  |
| Certification (IEC/IEEE/EN)         | -    | IEC 62116, IEC 61727, IEC 61683, IEC 60068, IEC 62109. |

### 9.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the model listed in Table 43.



#### Table 43: Inverter warranty

| Make                 | Warranty |
|----------------------|----------|
| ABB PVS800-57-1000kW | 5 years  |

### 9.2.3. Inverter Duty Transformer

Table 44 presents the key technical characteristics of the selected Shilchar transformer.

| Parameter                  | Unit | Shilchar                       | Shilchar                       |
|----------------------------|------|--------------------------------|--------------------------------|
| Rating                     | kVA  | 2200                           | 1100                           |
| Туре                       |      | ONAN, Oil Immersed,<br>Outdoor | ONAN, Oil Immersed,<br>Outdoor |
| Phases                     | No.  | 3                              | 3                              |
| Frequency                  | Hz   | 50                             | 50                             |
| Voltage                    | kV   | 0.4/0.4/11 kV                  | 0.4/11 kV                      |
| Windings                   | No.  | 3 (1 HV, 2 LV)                 | 2 (1 HV, 1 LV)                 |
| Vector Group               |      | Dy11y11                        | Dy11                           |
| Impedance at principal tap | %    | 6.25                           | 6.25                           |

#### Table 44: Technical characteristics of IDT

## 9.3. Project Design

### 9.3.1. DC Configuration

The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 36 MWp which is connected to 30 inverters of 30 MW cumulative capacity. 21 modules form a string and there are a total of 5,532 such strings. The fixed tilt Module Mounting Structure at 8° tilt angle has been considered. The DC to AC ratio for inverters are 1.2. Figure 38 show the actual photographs of PV array area.

#### Figure 38: Solar PV Array





## 9.3.2. AC Configuration

As per the submitted SLD for there are 30 nos. of inverters which are connected to the 14 nos. of three winding IDT of 2.2 MVA, 0.4/0.4/11 kV and 2 nos. of two winding IDT of 1.1 MVA, 0.4/11 kV rating. The output of IDT further connected to the 2-in-1 out 11 kV switchgear panel. There are such 8 nos of 11 kV outdoor switchgear panels. All 11 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices. The output of 2-in-1 out switchgear panel further connected to main HT panel at MCR building. The MCR 11 kV HT panel has 8 no. of incoming cable feeders from 11 kV switchgear panels, two auxiliary transformer feeder, two spare feeders and two outgoing cable feeders. The 11 kV switchgear panel are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. has been furnished by the Client.


### Figure 39: Indoor Switchyard



## 9.4. Power evacuation

The combined generated 30 MW power at 11 kV further step up to 110 kV via two nos. of 15 MVA, 110/11 kV power transformer. The elevated power 110 kV further evacuated to Grid Sub Station (GSS) via 110 kV Single Circuit (S/C) transmission line. The 110 kV transmission line is approx. 5.5 km away from the plant end substation.





# 10. UMD 25 MW (12 MW + 13 MW)

## 10.1. About Project

The 12 MW Project is located at Ondioulinayakanoor village, Aruppukottai Taluk, Virudunagar District in Tamilnadu state of India. The Project was constructed by EPC Contractor; M/s. M/s. Sterling & Wilson Pvt. Ltd, and operational since 26<sup>th</sup> March 2016. Currently the O&M contractor is AVI Solar Energy.


The Project is situated 13 km away from Virudunagar district headquarters. The nearest railway station is at Virudunagar railway which is around 15 km away from the site. The nearest airport to the project site is at Madurai Airport which is 60 km away. The Project site is well connected.

The 13 MW Project is located at Kattarankulam village, Tuticorin District in Tamilnadu state of India. The Project was constructed by EPC Contractor; M/s. M/s. Sterling & Wilson Pvt. Ltd, and operational since 26<sup>th</sup> March 2016. Currently the O&M contractor is AVI Solar Energy

The Project is situated 80 km away from Tuticorin district headquarters. The nearest railway station is at Tiruvannamalai railway which is around 25 km away from the site. The nearest airport to the project site is at Tuticorin Airport which is 90 km away. The Project site is well connected.



Figure 41: UMD 12 MW



#### Figure 42: UMD 13 MW








Figure 43:UMD 12 MW – Satellite image of project layout

Figure 44:UMD 13 MW – Satellite image of project layout



## 10.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 45 and Table 46.



| Component | Make and Model           | Quantity |
|-----------|--------------------------|----------|
| Module    | JA solar JAP6-72-310-3BB | 23,226   |
|           | JA solar JAP6-72-315-3BB | 22,869   |
| Inverter  | ABB PVS800-57-1000kW     | 12       |
| IDT       | Voltamp 2.2 MVA          | 6        |

| Table 46: | Summary | of key | components for 13 MW |  |
|-----------|---------|--------|----------------------|--|
|           |         |        |                      |  |

| Component | Make and Model           | Quantity |
|-----------|--------------------------|----------|
| Module    | JA solar JAP6-72-310-3BB | 11,508   |
|           | JA solar JAP6-72-315-3BB | 38,220   |
| Inverter  | ABB PVS800-57-1000kW     | 13       |
| IDT       | Voltamp 2.2 MVA          | 6        |
|           | Voltamp 1.1 MVA          | 1        |

### 10.2.1. PV modules

Table 47 presents the main technical characteristics of the installed PV modules.

| Parameter                   | UoM  | JA Solar        | JA Solar        |
|-----------------------------|------|-----------------|-----------------|
| Technology                  |      | Polycrystalline | Polycrystalline |
| Peak power (Pmax)           | W    | 310             | 315             |
| Voltage at Pmax (Vmpp)      | V    | 37.00           | 37.28           |
| Current at Pmax (Impp)      | А    | 8.38            | 8.45            |
| Open Circuit Voltage (Voc)  | V    | 45.45           | 45.60           |
| Short Circuit Current (Isc) | А    | 8.85            | 8.91            |
| Maximum system voltage      | V    | 1000            | 1000            |
| Temp coefficient of Pmax    | %/°C | -0.41           | -0.41           |
| Module efficiency           | %    | 15.99           | 16.25           |
| Degradation                 | %    | 0.7%            | 0.7%            |
| Certification               | -    | IEC 61215,      | IEC 61215,      |
|                             |      | IEC 61730,      | IEC 61730,      |
|                             |      | CE Certified,   | CE Certified,   |
|                             |      | ISO 9001,       | ISO 9001,       |
|                             |      | ISO 14001       | ISO 14001       |

#### Table 47: Technical characteristics of PV modules

### 10.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.



### 10.2.2. Inverter

Table 48 presents the main technical characteristics of the selected model.

| Parameter              | Unit | ABB                       |
|------------------------|------|---------------------------|
| Model                  | -    | PVS800-57-1000kW          |
| Max. efficiency        | %    | 98.8                      |
| Max. DC input voltage  | V    | 1,100                     |
| Max. DC current        | А    | 1,710                     |
| MPPT operating voltage | V    | -                         |
| range                  |      |                           |
| Number of MPP          | no.  | 1                         |
| independent inputs     |      |                           |
| Max. AC output power   | kW   | 1000                      |
| Max. AC output current | А    | 1445                      |
| Nominal AC voltage     | V    | 405                       |
| Certification          | -    | IEC 62116, IEC 61727, IEC |
| (IEC/IEEE/EN)          |      | 61683, IEC 60068,         |
|                        |      | IEC 62109.                |

### Table 48: Technical characteristics of Inverter

### 10.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the models listed in Table 49.

#### Table 49: Inverter warranty

| Make                 | Warranty |
|----------------------|----------|
| ABB PVS800-57-1000kW | 5 years  |

### 10.2.3. Inverter Duty Transformer

Table 50 presents the key technical characteristics of the selected Shilchar transformer.

#### Table 50: Technical characteristics of IDT

| Parameter                  | Unit | Voltamp                        | Voltamp                        |
|----------------------------|------|--------------------------------|--------------------------------|
| Rating                     | kVA  | 2200                           | 1100                           |
| Туре                       |      | ONAN, Oil Immersed,<br>Outdoor | ONAN, Oil Immersed,<br>Outdoor |
| Phases                     | No.  | 3                              | 3                              |
| Frequency                  | Hz   | 50                             | 50                             |
| Voltage                    | kV   | 0.4/0.4/33kV                   | 0.4/0.4/33kV                   |
| Windings                   | No.  | 3 (1 HV, 2 LV)                 | 2 (1 HV, 1 LV)                 |
| Vector Group               |      | Dy11y11                        | Dy11y11                        |
| Impedance at principal tap | %    | 6                              | 6                              |



## 10.3. Project Design

## 10.3.1. DC Configuration

The design configuration for the UMD 12 MW project has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 14.41 MWp which is connected to 12 inverters of 12 MW cumulative capacity. 21 modules form a string and there are a total of 2,195 such strings. The fixed tilt Module Mounting Structure at 8° tilt angle has been considered. The DC to AC ratio for inverters are 1.2.

The design configuration for the UMD 13 MW project has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 15.6 MWp which is connected to 30 inverters of 30 MW cumulative capacity. 21 modules form a string and there are a total of 2,368 such strings. The fixed tilt Module Mounting Structure at 8° tilt angle has been considered. The DC to AC ratio for inverters are 1.2.

## 10.3.2. AC Configuration

As per the SLD for UMD 12 MW project, there are 12 nos. of inverters which are connected to the 6 nos. of three winding IDT of 2.2 MVA, 0.4/0.4/33 kV rating. There total four no of 33 kV outdoor switchgear panels are at site. 2 of 4 have 2-in-1 out combination and other 2 have 1-in-1 out combination. In 2-in-1 out combination there are two incoming IDT feeders and one outgoing feeder. Similarly, In 1-in-1 out combination there is one incoming IDT feeders and one outgoing feeder. All 33 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices. The output of both 1-in-1 out and 2-in-1 out 33 kV outdoor switchgear panel further connected to main 33 kV HT panel at MCR building. The main HT panel have four no of incoming cable feeder from PV plant side and one outgoing cable feeder. The 33 kV switchgear panel are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. has been furnished by the Client.

As per the SLD of UMD 13MW project, there are 13 nos. of inverters which are connected to the 6 nos. of three winding IDT of 2.2 MVA, 0.4/0.4/33 kV and 1 no of two winding IDT of 1.1 MVA, 0.4/ 33 kV rating. There total three no of 33 kV outdoor switchgear panels are at site. The 33 kV switchgear panel have 2-in-1 out combination. In 2-in-1 out combination there are two incoming IDT feeders and one outgoing feeder. All 33 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices. The output of both 2-in-1 out 33 kV outdoor switchgear panel further connected to main 33 kV HT panel at MCR building. The main HT panel have four no of incoming cable feeder from PV plant side and one outgoing cable feeder. The 33 kV switchgear panel are equipped with all necessary protection devices which includes




instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. has been furnished by the Client.

## 10.4. Power evacuation


The combined generated 12 MW power at 33 kV further converted from cable feeder to overhead line feeder with the help of double pole structure. The combined power further evacuated to GN Patti Grid Substation via 33 kV transmission line. The transmission line length is 5.5 km.

### Figure 45: Power Evacuation Schematic



Similarly, the combined generated 13 MW power at 33 kV further converted from cable feeder to overhead line feeder with the help of double pole structure. The combined power further evacuated to M.Duraisamypuram Grid Substation via 33 kV transmission line. The transmission line length is 8.75 km.

### Figure 46: Power Evacuation Schematic



## 11. TN Solar Thuthookudi

### 11.1. About Project

The Project is located at Chithavanaickenpatti village, Villathikulam Taluka, Tuticorin, District Tamilnadu of India. The Project was constructed by EPC Contractor; M/s. M/s. Sterling & Wilson Pvt. Ltd, and has been operational since 31<sup>st</sup> October 2015. Currently the O&M contractor is AVI Solar Energy.

The Project is situated 50 km away from Tuticorin district headquarters. The nearest railway station is at Tiruvannamalai railway which is around 45 km away from the site. The nearest airport to the project site is at Tuticorin Airport which is 60 km away. The Project site is well connected.






Figure 47: TN Solar Thuthookudi

Figure 48: TN Solar Thuthookudi – Satellite image of project layout





## 11.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 51.

| Table 51: | Summary | of key | components |
|-----------|---------|--------|------------|
|-----------|---------|--------|------------|

| Component | Make and Model           | Quantity |
|-----------|--------------------------|----------|
| Module    | JA solar JAP6-72-310-3BB | 23,184   |
|           | JA solar JAP6-72-315-3BB | 15,288   |
| Inverter  | ABB PVS800-57-1000kW     | 10       |
| IDT       | Voltamp 2.2 MVA          | 5        |

### 11.2.1. PV modules

Table 52 presents the main technical characteristics of the installed PV modules.

### Table 52: Technical characteristics of PV modules

| Parameter                   | UoM  | JA Solar  | JA Solar  |
|-----------------------------|------|---|---|
| Technology                  |      | Polycrystalline   |   |
| Peak power (Pmax)           | W    | 310   | 315   |
| Voltage at Pmax (Vmpp)      | V    | 37.00   | 37.28   |
| Current at Pmax (Impp)      | А    | 8.38  | 8.45  |
| Open Circuit Voltage (Voc)  | V    | 45.45   | 45.60   |
| Short Circuit Current (Isc) | А    | 8.85  | 8.91  |
| Maximum system voltage      | V    | 1000  | 1000  |
| Temp coefficient of Pmax    | %/°C | -0.41   | -0.41   |
| Module efficiency           | %    | 15.99   | 16.25   |
| Degradation                 | %    | 0.7%  | 0.7%  |
| Certification               | -    | IEC 61215, IEC 61730,<br>CE Certified, ISO 9001,<br>ISO 14001 | IEC 61215, IEC 61730,<br>CE Certified, ISO 9001,<br>ISO 14001 |

### 11.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

### 11.2.2. Inverter

Table 53 presents the main technical characteristics of the selected model.



| Parameter                    | Unit | Description           |
|------------------------------|------|-----------------------|
| Model                        | -    | PVS800-57-1000kW      |
| Max. efficiency              | %    | 98.8                  |
| Max. DC input voltage        | V    | 1,100                 |
| Max. DC current              | А    | 1,710                 |
| MPPT operating voltage range | V    | -                     |
| Number of MPP independent    | no.  | 1                     |
| inputs                       |      |                       |
| Max. AC output power         | kW   | 1000                  |
| Max. AC output current       | А    | 1445                  |
| Nominal AC voltage           | V    | 405                   |
| Certification (IEC/IEEE/EN)  | -    | IEC 62116, IEC 61727, |
|                              |      | IEC 61683, IEC 60068, |
|                              |      | IEC 62109.            |

### 11.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the models listed in Table 54.

#### Table 54: Inverter warranty

| Make                 | Warranty |
|----------------------|----------|
| ABB PVS800-57-1000kW | 5 years  |

### 11.2.3. Inverter Duty Transformer

Table 55 presents the key technical characteristics of the selected Voltamp transformer.

| Parameter                  | Unit | Description                 |  |
|----------------------------|------|-----------------------------|--|
| Rating                     | kVA  | 2200                        |  |
| Туре                       |      | ONAN, Oil Immersed, Outdoor |  |
| Phases                     | No.  | 3                           |  |
| Frequency                  | Hz   | 50                          |  |
| Voltage                    | kV   | 0.4/0.4/33kV                |  |
| Windings                   | No.  | 3 (1 HV, 2 LV)              |  |
| Vector Group               |      | Dy11y11                     |  |
| Impedance at principal tap | %    | 6                           |  |

#### Table 55: Technical characteristics of IDT

## 11.3. Project Design

## 11.3.1. DC Configuration

The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 12 MWp which is connected to 10 inverters of 10 MW cumulative capacity. 21 modules form a string and there are a total of 1,832 such strings.



The fixed tilt Module Mounting Structure at 8° tilt angle has been considered. The DC to AC ratio for inverters are 1.2.


## 11.3.2. AC Configuration

As per the submitted SLD for there are 5 nos. of inverters which are connected to the 10 nos. of three winding IDT of 2.2 MVA, 0.4/0.4/33 kV rating. The output of IDT further connected to two nos. of 2-in-1 out 33 kV switchgear panel. All 33 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices. The output of 2-in-1 out switchgear panel further connected to main 33 kV HT panel at MCR building. The MCR 33 kV HT panel has 2 no. of incoming cable feeders from 33 kV switchgear panels, one from IDT and one outgoing cable feeders. The 33 kV switchgear panel are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection devices which includes instantaneous and inverse time phase and earth fault over-current protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. has been furnished by the Client.

## 11.4. Power evacuation

The combined generated 10 MW power at 33 kV further converted from cable feeder to overhead line feeder with the help of double pole structure. The combined power further evacuated to Vilathikulam Grid Substation via 33 kV transmission line. The transmission line length is 7.2 km.

### Figure 49: Power Evacuation Schematic



## 12. TN Solar Virudhunagar

## 12.1. About Project

The Project is located at Aruppukkottai village, Virudhunagar, District Tamilnadu of India. The Project was constructed by EPC Contractor; M/s. M/s. Sterling & Wilson Pvt. Ltd, and has been operational since 31<sup>st</sup> October 2015. Currently the O&M contractor is AVI Solar Energy.

The Project is situated 35 km away from Virudhunagar district headquarters. The nearest railway station is at Virudhunagar railway which is around 32 km away from the site. The nearest airport to the project site is at Madurai Airport which is 60 km away. The Project site is well connected.



Figure 50: TN Solar Virudhunagar




Figure 51: TN Solar Virudhunagar – Satellite image of project layout





## 12.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 56.

| Component | Make and Model           | Quantity |  |  |
|-----------|--------------------------|----------|--|--|
| Module    | JA solar JAP6-72-310-3BB | 23,184   |  |  |
|           | JA solar JAP6-72-315-3BB | 15,288   |  |  |
| Inverter  | ABB PVS800-57-1000kW     | 8        |  |  |
| IDT       | Voltamp 2.2 MVA          | 4        |  |  |

#### Table 56: Summary of key components

### 12.2.1. PV modules

Table 57 presents the main technical characteristics of the installed PV modules.

| Parameter                   | UoM  | JA Solar        | JA Solar        |
|-----------------------------|------|-----------------|-----------------|
| Technology                  |      | Polycrystalline | Polycrystalline |
| Peak power (Pmax)           | W    | 310             | 315             |
| Voltage at Pmax (Vmpp)      | V    | 37.00           | 37.28           |
| Current at Pmax (Impp)      | А    | 8.38            | 8.45            |
| Open Circuit Voltage (Voc)  | V    | 45.45           | 45.60           |
| Short Circuit Current (Isc) | А    | 8.85            | 8.91            |
| Maximum system voltage      | V    | 1000            | 1000            |
| Temp coefficient of Pmax    | %/°C | -0.41           | -0.41           |
| Module efficiency           | %    | 15.99           | 16.25           |
| Degradation                 | %    | 0.7%            | 0.7%            |
| Certification               | -    | IEC 61215,      | IEC 61215,      |
|                             |      | IEC 61730,      | IEC 61730,      |
|                             |      | CE Certified,   | CE Certified,   |
|                             |      | ISO 9001,       | ISO 9001,       |
|                             |      | ISO 14001       | ISO 14001       |

#### Table 57: Technical characteristics of PV modules

### 12.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

### 12.2.2. Inverter

Table 58 presents the main technical characteristics of the selected model.



| Parameter                           | Unit | ABB  |
|-------------------------------------|------|--|
| Model                               | -    | PVS800-57-1000kW                                       |
| Max. efficiency                     | %    | 98.8   |
| Max. DC input voltage               | V    | 1,100  |
| Max. DC current                     | А    | 1,710  |
| MPPT operating voltage range        | V    | -  |
| Number of MPP<br>independent inputs | no.  | 1  |
| Max. AC output power                | kW   | 1000   |
| Max. AC output current              | А    | 1445   |
| Nominal AC voltage                  | V    | 405  |
| Certification<br>(IEC/IEEE/EN)      | -    | IEC 62116, IEC 61727, IEC 61683, IEC 60068, IEC 62109. |

### Table 58: Technical characteristics of Inverter

### 12.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the models listed in Table 43.

#### Table 59: Inverter warranty

| Make                 | Warranty |
|----------------------|----------|
| ABB PVS800-57-1000kW | 5 years  |

### 12.2.3. Inverter Duty Transformer

Table 60 presents the key technical characteristics of the selected Voltamp transformer.

| Parameter                  | Unit | Voltamp                     |  |
|----------------------------|------|-----------------------------|--|
| Rating                     | kVA  | 2200                        |  |
| Туре                       |      | ONAN, Oil Immersed, Outdoor |  |
| Phases                     | No.  | 3                           |  |
| Frequency                  | Hz   | 50                          |  |
| Voltage                    | kV   | 0.4/0.4/33 kV               |  |
| Windings                   | No.  | 3 (1 HV, 2 LV)              |  |
| Vector Group               |      | Dy11y11                     |  |
| Impedance at principal tap | %    | 6                           |  |

#### Table 60: Technical characteristics of IDT

## 12.3. Project Design

## 12.3.1. DC Configuration



The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 9.6 MWp which is connected to 8 inverters of 8 MW cumulative capacity. 21 modules form a string and there are a total of 1,464 such strings. The fixed tilt Module Mounting Structure at 8° tilt angle has been considered. The DC to AC ratio for inverters are 1.2.

## 12.3.2. AC Configuration

As per the submitted SLD for there are 8 nos. of inverters which are connected to the 4 nos. of three winding IDT of 2.2 MVA, 0.4/0.4/33 kV rating. The output of one IDT is directly connected to 33 kV main switchgear panel at MCR Building. However, the output of the remaining three IDTs further connected to the 2-in-1 out 33 kV switchgear panel and 1-in-1 out 33 kV switchgear panel. There are such two nos. of 33 kV outdoor switchgear panels one is 2-in-1 out 33 kV switchgear panel and another one is 1-in-1 out 33 kV switchgear panel. The 1-in-1 out switchgear panel has one incoming feeder from IDT and one outgoing feeder to 33kV main HT panel. Similarly, the 2-in-1 out switchgear panel have two incoming feeder from IDT and one outgoing feeder to 33kV main HT panel.


All 33 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices.

The 33 kV main HT panel has two nos. of incoming cable feeders from 33 kV switchgear panels, one incoming feeder from IDT and one outgoing cable feeder. The 33 kV switchgear panel are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. has been furnished by the Client.

## 12.4. Power evacuation

The combined generated 8 MW power at 33 kV further converted from cable feeder to overhead line feeder with the help of double pole structure. The combined power further evacuated to Vilathikulam Grid Substation via 33 kV transmission line. The transmission line length is 7.2 km.

### Figure 52: Power Evacuation Schematic





## 13. TN Solar Dindigul

### 13.1. About Project

The Project is located at Vedasandur Village, Dindigul, District Tamilnadu of India. The Project was constructed by EPC Contractor; M/s. M/s. Sterling & Wilson Pvt. Ltd, and has been operational since 28<sup>th</sup> December 2015. Currently the O&M contractor is AVI Solar Energy.

The Project is situated 27 km away from Dindigul district headquarters. The nearest railway station is at Dindigul railway which is around 26 km away from the site. The nearest airport to the project site is at Madurai Airport which is 120 km away. The Project site is well connected.









Figure 54: TN Solar Dindigul– Satellite image of project layout

## 13.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 61

| Component | Make and Model           | Quantity |  |  |
|-----------|--------------------------|----------|--|--|
| Module    | JA solar JAP6-72-310-3BB | 23,184   |  |  |
|           | JA solar JAP6-72-315-3BB | 15,288   |  |  |
| Inverter  | ABB PVS800-57-1000kW     | 10       |  |  |
| IDT       | Voltamp 2.2 MVA          | 2        |  |  |
|           | Voltamp 1.1 MVA          | 1        |  |  |

### Table 61: Summary of key components

### 13.2.1. PV modules

Table 62 presents the main technical characteristics of the installed PV modules.

| Parameter              | UoM | JA Solar        | JA Solar |
|------------------------|-----|-----------------|----------|
| Technology             |     | Polycrystalline |          |
| Peak power (Pmax)      | W   | 310             | 315      |
| Voltage at Pmax (Vmpp) | V   | 37.00           | 37.28    |
| Current at Pmax (Impp) | A   | 8.38            | 8.45     |

#### Table 62: Technical characteristics of PV modules



| Parameter                   | UoM  | JA Solar  | JA Solar  |
|-----------------------------|------|---|---|
| Open Circuit Voltage (Voc)  | V    | 45.45   | 45.60   |
| Short Circuit Current (Isc) | A    | 8.85  | 8.91  |
| Maximum system voltage      | V    | 1000  | 1000  |
| Temp coefficient of Pmax    | %/°C | -0.41   | -0.41   |
| Module efficiency           | %    | 15.99   | 16.25   |
| Degradation                 | %    | 0.7%  | 0.7%  |
| Certification               | -    | IEC 61215,<br>IEC 61730,<br>CE Certified,<br>ISO 9001,<br>ISO 14001 | IEC 61215,<br>IEC 61730,<br>CE Certified,<br>ISO 9001,<br>ISO 14001 |

### 13.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees power output at the end of 25<sup>th</sup> year.

### 13.2.2. Inverter

Table 63 presents the main technical characteristics of the selected model.

| Parameter                           | Unit | ABB  |
|-------------------------------------|------|--|
| Model                               | -    | PVS800-57-1000kW   |
| Max. efficiency                     | %    | 98.8   |
| Max. DC input voltage               | V    | 1,100  |
| Max. DC current                     | А    | 1,710  |
| MPPT operating voltage range        | V    | -  |
| Number of MPP<br>independent inputs | no.  | 1  |
| Max. AC output power                | kW   | 1000   |
| Max. AC output current              | А    | 1445   |
| Nominal AC voltage                  | V    | 405  |
| Certification<br>(IEC/IEEE/EN)      | -    | IEC 62116, IEC 61727, IEC<br>61683, IEC 60068,<br>IEC 62109. |

#### Table 63: Technical characteristics of Inverter

### 13.2.2.1. Warranty

The inverters are with standard product warranty of 5 years for the models listed in Table 64.



#### Table 64: Inverter Warrantv

| Make                 | Warranty |
|----------------------|----------|
| ABB PVS800-57-1000kW | 5 years  |

### 13.2.3. Inverter Duty Transformer

Table 65 presents the key technical characteristics of the selected Voltamp transformer.

| Table 65: Technical characteristics of IDT |      |         |  |  |
|--|------|---------|--|--|
| Parameter                                  | Unit | Voltamp |  |  |

| Parameter                  | Unit | Voltamp                        | Voltamp                        |
|----------------------------|------|--------------------------------|--------------------------------|
| Rating                     | kVA  | 2200                           | 1100                           |
| Туре                       |      | ONAN, Oil Immersed,<br>Outdoor | ONAN, Oil Immersed,<br>Outdoor |
| Phases                     | No.  | 3                              | 3                              |
| Frequency                  | Hz   | 50                             | 50                             |
| Voltage                    | kV   | 0.4/0.4/11 kV                  | 0.4/11 kV                      |
| Windings                   | No.  | 3 (1 HV, 2 LV)                 | 2 (1 HV, 1 LV)                 |
| Vector Group               |      | Dy11y11                        | Dy11                           |
| Impedance at principal tap | %    | 6                              | 6                              |

## 13.3. Project Design

## 13.3.1. DC Configuration

The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 6 MWp which is connected to 5 inverters of 5 MW cumulative capacity. 21 modules form a string and there are a total of 916 such strings. The fixed tilt Module Mounting Structure at 8° tilt angle has been considered. The DC to AC ratio for inverters are 1.2.

## 13.3.2. AC Configuration

As per the submitted SLD for there are 5 nos. of inverters which are connected to the two nos. of three winding IDT of 2.2 MVA, 0.4/0.4/11 kV rating and one no of two winding IDT of 1.1 MVA, 0.4/11 kV rating. The output of one IDT is directly connected to 11 kV main switchgear panel at MCR Building. However, the output of the remaining two IDTs further connected to the 2-in-1 out 11 kV switchgear panel. The 2-in-1 out switchgear panel have two incoming feeder from IDT and one outgoing feeder to 11 kV main HT panel. The 11 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices.

The 11 kV main HT panel has one incoming cable feeders from 11 kV switchgear panels, one incoming feeder from IDT and one outgoing cable feeder. The 11 kV switchgear panel are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip




circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. has been furnished by the Client.

## 13.4. Power evacuation

The combined generated 5 MW power at 11 kV further converted from cable feeder to overhead line feeder with the help of double pole structure. The combined power further evacuated to Vilathikulam Grid Substation via 11 kV transmission line. The transmission line length is 7.2 km.

### Figure 55: Power Evacuation Schematic



## 14. USUPL Bap

### 14.1. About Project

The Project is located at Manchitiya Village, Bap Tehsil, District Jodhpur, Rajasthan state of India. The Project was constructed by EPC Contractor; M/s. Jackson and has been operational since 26<sup>th</sup> March 2013. Currently the O&M contractor is Mahindra Teqo.

The Project is situated 15 km away from Bap district headquarters. The nearest railway station is at Jodhpur railway which is around 180 km away from the site. The nearest airport to the project site is at Jodhpur Airport which is 185 km away. The Project site is well connected.



#### Figure 56: USUPL Bap



Figure 57: USUPL Bap- Satellite image of project layout



## 14.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 66.



| Table 66: | Summary of key components |
|-----------|---------------------------|
|-----------|---------------------------|

| Component | Make and Model                   | Quantity |
|-----------|----------------------------------|----------|
| Module    | Jinko Solar JKM545M-72HL4-V      | 29,355   |
|           | Trina Solar Trina 295            | 1,500    |
|           | JA solar JAP6-72-300/3BB         | 9,520    |
|           | Vikram solar Eldora 60.255.03.04 | 25,800   |
| Inverter  | Schneider Electric               | 46       |
|           | Conext Core XC-680               |          |
| IDT       | Raychem 1.6 MVA, 0.38/0.38/33kV  | 14       |
|           | Raychem 0.8 MVA 0.38/11 kV       | 2        |

### 14.2.1. PV modules

Table 67 presents the main technical characteristics of the installed PV modules.

| Parameter                   | UoM  | Jinko Solar  | JA Solar  | Vikram solar   | Trina  |
|-----------------------------|------|--|---|--|--|
| Technology                  |      | Mono-<br>PERC  | Polycrystalli<br>ne   | Polycrystallin<br>e  | Polycrystallin<br>e  |
| Peak power (Pmax)           | W    | 545  | 300   | 255  | 295  |
| Voltage at Pmax (Vmpp)      | V    | 40.80  | 36.41   | 30.8   | 32.2   |
| Current at Pmax (Impp)      | А    | 13.36  | 8.24  | 8.29   | 9.01   |
| Open Circuit Voltage (Voc)  | V    | 49.42  | 45.20   | 37.7   | 39.5   |
| Short Circuit Current (Isc) | А    | 13.94  | 8.73  | 8.82   | 9.5  |
| Maximum system voltage      | V    | 1000/1500  | 1000  | 1000   | 1000   |
| Temp coefficient of Pmax    | %/°C | -0.35  | -0.41   | -0.41  | -0.39  |
| Module efficiency           | %    | 21.13  | 15.48   | 15.7   | 17.7   |
| Degradation                 | %    | 0.5  | 0.7   | 0.7  | 0.7  |
| Certification               | -    | IEC 61215,<br>IEC 61730,<br>ISO 9001,<br>ISO 14001,<br>ISO 45001 | IEC 61215,<br>IEC 61730,<br>CE Certified,<br>ISO 9001,<br>ISO 14001 | IEC 61215,<br>IEC 61730,<br>IEC 62716,<br>IEC 62804,<br>CE Certified | IEC 61215,<br>IEC 61730,<br>IEC 62716,<br>CE Certified,<br>TUV Certified |

#### Table 67: Technical characteristics of PV modules

#### 14.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

### 14.2.2. Inverter

Table 68 presents the main technical characteristics of the selected model.



| Parameter              | Unit | Schneider Electric   |
|------------------------|------|----------------------|
| Model                  | -    | Conext Core XC-680   |
| Max. efficiency        | %    | 98.9                 |
| Max. DC input voltage  | V    | 1000                 |
| Max. DC current        | А    | 1280                 |
| MPPT operating voltage | V    | 550 to 800           |
| range                  |      |                      |
| Number of MPP          | no.  | -                    |
| independent inputs     |      |                      |
| Max. AC output power   | kW   | 680                  |
| Nominal AC voltage     | V    | 380                  |
| Certification          | -    | IEC 61000, IEC62103, |
| (IEC/IEEE/EN)          |      | IEC 61727, IEC62116, |
|                        |      | IEC 62109.           |

#### Table 68: Technical characteristics Inverter

#### 14.2.2.1. Warranty

Table 69 presents the Inverter product warranty:

#### Table 69: Inverter Warranty

| Make                                     | Warranty |
|--|----------|
| Schneider Electric<br>Conext Core XC-680 | 5 years  |

### 14.2.3. Inverter Duty Transformer

Table 70 presents the key technical characteristics of the selected Raychem transformer.

| Parameter                  | Unit | Raychem                           | Raychem                        |
|----------------------------|------|-----------------------------------|--------------------------------|
| Rating                     | kVA  | 2000                              | 4000                           |
| Туре                       |      | ONAN, Oil<br>Immersed,<br>Outdoor | ONAN, Oil Immersed,<br>Outdoor |
| Phases                     | No.  | 3                                 | 3                              |
| Frequency                  | Hz   | 50                                | 50                             |
| Voltage                    | kV   | 0.38/0.38/11kV                    | 0.38/0.38/0.38/0.38/11kV       |
| Windings                   | No.  | 3 (1 HV, 2 LV)                    | 5 (1 HV, 4 LV)                 |
| Vector Group               |      | Dy11y11                           |                                |
| Impedance at principal tap | %    | 6.25                              |                                |

#### Table 70: Technical characteristics of IDT

### 14.3. Project Design

### 14.3.1. DC Configuration



The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 25.88 MWp which is connected to 46 inverters of 20.4 MW cumulative capacity. 19 and 20 modules form a string and there are a total of 1,545 and 1,841 strings respectively. The fixed tilt Module Mounting Structure at 8° tilt angle has been considered. The DC to AC ratio for inverters are 1.2.


### 14.3.2. AC Configuration

As per the submitted SLD for there are 46 nos. of inverters which are connected to the 22 nos. of three winding IDT of 1.6 MVA, 0.38/0.8/33 kV rating and one no of two winding IDT of 0.8 MVA, 0.38/33 kV rating. The output of every two IDT is connected to 33 kV RMU panel. There are such 12 RMU panels at site. All RMU panels are equipped with all necessary protection system which includes both transformer electrical and mechanical protections. All RMU panel interconnected with each other. The combined power further evacuated to main 33 kV switchgear panel at site via 2 no's of cable feeders. The 33 kV main HT panel has two incoming cable feeders from RMU panels and one outgoing cable feeder. The 33 kV switchgear panel are equipped with all necessary protection devices.

### 14.4. Power evacuation

The combined generated 20 MW power at 33 kV further converted from cable feeder to overhead line feeder with the help of double pole structure. The combined power further evacuated to 132 kV Bap Grid Substation via 33 kV transmission line. The transmission line length is 8 km.

#### Figure 58: Power Evacuation Schematic





### 15. USUPL Mohoba

### 15.1. About Project

The Project is located at Kankua Village, Mahoba district, Uttar Pradesh state of India. The Project was constructed by EPC Contractor; M/s. Sukhbir Agro and has been operational since 25<sup>th</sup> September 2013. Currently the O&M contractor is Meera.

The Project is situated 65 km away from Mahoba district headquarters. The nearest railway station is at Naugao railway which is around 25 km away from the site. The nearest airport to the project site is at Gwalior Airport which is 215 km away. The Project site is well connected.

#### Figure 61: USUPL Mahoba







### Figure 62: USUPL Mahoba – Satellite image of project layout

#### 15.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 71

| Component | Make and Model                          | Quantity |  |
|-----------|---|----------|--|
| Module    | Canadian solar CS6U-320P                | 115,560  |  |
| Inverter  | ABB PVS800-57-1000kW                    | 30       |  |
| Tracker   |   |          |  |
| IDT       | Raychem 4 MVA 0.38/0.38/0.38/0.38/11 kV | 7        |  |
|           | Raychem 2 MVA 0.38/0.38/11 kV           | 1        |  |

#### Table 71: Summary of key components

### 15.2.1. PV modules

Table 72 presents the main technical characteristics of the installed PV modules.

| Table 72: Technical characteristics of PV module |     |                 |  |
|--|-----|-----------------|--|
| Parameter  | UoM | Canadian solar  |  |
| Technology                                       |     | Polycrystalline |  |
| Peak power (Pmax)                                | W   | 320             |  |
| Voltage at Pmax (Vmpp)                           | V   | 36.8            |  |
| Current at Pmax (Impp)                           | А   | 8.69            |  |



| Parameter                   | UoM  | Canadian solar  |
|-----------------------------|------|---|
| Open Circuit Voltage (Voc)  | V    | 45.3  |
| Short Circuit Current (Isc) | А    | 9.26  |
| Maximum system voltage      | V    | 1000  |
| Temp coefficient of Pmax    | %/°C | -0.41   |
| Module efficiency           | %    | 16.46   |
| Degradation                 | %    | 0.7%  |
| Certification               | -    | IEC 61215, IEC 61730,<br>IEC 61701, IEC 62716<br>CE Certified |

#### 15.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

### 15.2.2. Inverter

Table 73 presents the main technical characteristics of the selected model.

| Parameter              | Unit | ABB            |
|------------------------|------|----------------|
| Model                  | -    | PVS800-57-     |
|                        |      | 1000kW         |
| Max. efficiency        | %    | 98.8           |
| Max. DC input voltage  | V    | 1,100          |
| Max. DC current        | A    | 1,710          |
| MPPT operating voltage | V    | -              |
| range                  |      |                |
| Number of MPP          | no.  | 1              |
| independent inputs     |      |                |
| Max. AC output power   | kW   | 1000           |
| Max. AC output current | A    | 1445           |
| Nominal AC voltage     | V    | 405            |
| Certification          | -    | IEC 62116, IEC |
| (IEC/IEEE/EN)          |      | 61727, IEC     |
|                        |      | 61683, IEC     |
|                        |      | 60068,         |
|                        |      | IEC 62109.     |

#### Table 73: Technical characteristics of Inverter



#### 15.2.2.1. Warranty

Table 74 presents the Inverter product warranty:

| Table | 74: | Inverter | warranty |
|-------|-----|----------|----------|
|       |     |          |          |

| Make                 | Warranty |
|----------------------|----------|
| ABB PVS800-57-1000kW | 5 years  |

### 15.2.3. Inverter Duty Transformer

Table 75 presents the key technical characteristics of the selected Raychem transformer.

| Parameter                  | Unit | Raychem                           | Raychem                        |
|----------------------------|------|-----------------------------------|--------------------------------|
| Rating                     | kVA  | 2000                              | 4000                           |
| Туре                       |      | ONAN, Oil<br>Immersed,<br>Outdoor | ONAN, Oil Immersed,<br>Outdoor |
| Phases                     | No.  | 3                                 | 3                              |
| Frequency                  | Hz   | 50                                | 50                             |
| Voltage                    | kV   | 0.38/0.38/11kV                    | 0.38/0.38/0.38/0.38/11kV       |
| Windings                   | No.  | 3 (1 HV, 2 LV)                    | 5 (1 HV, 4 LV)                 |
| Vector Group               |      | Dy11y11                           |                                |
| Impedance at principal tap | %    | 6.25                              |                                |

#### Table 75: Technical characteristics of IDT


### 15.3. Project Design

### 15.3.1. DC Configuration

The design configuration for the fixed tilt project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 31.9 MWp which is connected to 26 inverters of 26 MW cumulative capacity. 20 modules form a string and there are a total of 4,992 strings. The fixed tilt Module Mounting Structure at 19° tilt angle has been considered. The DC to AC ratio for inverters are 1.23.

Similarly, the design configuration for the tracker system project has been considered. The installed DC capacity of the project is 5 MWp which is connected to 4 inverters of 4 MW capacity. 20 modules form a string and there are a total of 786 strings. The DC to AC ratio for inverters are 1.26. Figure 63 and Figure 64 show the actual photographs of PV array area and ICR.





### 15.3.2. AC Configuration

As per the submitted SLD for there are 30 nos. of inverters which are connected to the seven nos. of five winding IDT of 4 MVA, 0.38/0.38/0.38/0.38/11 kV rating and one no of two winding IDT of 2 MVA, 0.38/0.38/11 kV rating. The output of each IDT is further connected to 11 kV outdoor VCB panel. The 1-in-1 out VCB panel have one incoming feeder from IDT and one outgoing feeder to 11 kV main HT panel. The 11 kV switchgear panels are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. along with transformer electrical and mechanical protection devices. The output of each 11 kV outdoor VCB panel further connected to the 11 kV main HT panel.

The 11 kV main HT panel has eight incoming cable feeders from 11 kV VCB panels, one spare feeder and two outgoing cable feeder. The 11 kV switchgear panel are equipped with all necessary protection devices which includes instantaneous and inverse time phase and earth fault over-current protection functions along with the master trip relay to ensure breaker tripping and trip circuit supervision relay for identification of anomaly in the trip circuit. Relevant indications like On, Off, Trip, Test position, Service position etc. has been furnished by the Client.

## 15.4. Power evacuation

The combined generated 30 MW power at 11 kV further step up to 132 kV via 2 nos. of 15/20 MVA, 132/11 kV power transformer at plant end. The elevated power from 11 kV to 132 kV evacuated to 132 kV Panwari Grid Substation via 132 kV transmission line. The transmission line length is around 10 km.



#### Figure 65: Power Evacuation Schematic




## 16. TL Kanji

### 16.1. About Project

The Project is located at Mahroni khurd Village, District Lalitpur, Uttarpradesh state of India. The Project was constructed by EPC Contractor; M/s. Jackson and has been operational since 19<sup>th</sup> March 2015. Currently the O&M contractor is AVI Solar Energy.

The Project is situated 15 km away from Lalitpur district headquarters. The nearest railway station is at Lalitpur railway which is around 20 km away from the site. The nearest airport to the project site is at Gwaliar Airport which is 200 km away. The Project site is well connected.



#### Figure 66: TL Kanji





### Figure 67: TL Kanji- Satellite image of project layout

## 16.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 76.

| Component | Make and Model                  | Quantity |
|-----------|---------------------------------|----------|
| Module    | Waaree WS-315_4BB               | 36,500   |
|           | Trina TSM 295                   | 1,360    |
|           | JA solar JAP6-72-300/3BB        | 1,720    |
| Inverter  | Schneider Electric              | 17       |
|           | Conext Core XC-680              |          |
| IDT       | Raychem 1.4 MVA, 0.38/0.38/33kV | 7        |
|           | Raychem 0.75 MVA 0.38/11 kV     | 1        |

#### Table 76: Summary of key components

### 16.2.1. PV modules

Table 77 presents the main technical characteristics of the installed PV modules.



| Parameter                   | UoM  | JA Solar      | Waaree         | Trina          |
|-----------------------------|------|---------------|----------------|----------------|
| Technology                  |      | Polycrystalli | Polycrystallin | Polycrystallin |
|                             |      | ne            | е              | е              |
| Peak power (Pmax)           | W    | 300           | 315            | 295            |
| Voltage at Pmax (Vmpp)      | V    | 36.41         | 32.9           | 32.2           |
| Current at Pmax (Impp)      | А    | 8.24          | 9.58           | 9.01           |
| Open Circuit Voltage (Voc)  | V    | 45.20         | 40.38          | 39.5           |
| Short Circuit Current (Isc) | А    | 8.73          | 9.9            | 9.5            |
| Maximum system voltage      | V    | 1000          | 1000           | 1000           |
| Temp coefficient of Pmax    | %/°C | -0.41         | -0.37          | -0.39          |
| Module efficiency           | %    | 15.48         | 18.92          | 17.7           |
| Degradation                 | %    | 0.7           | 0.7            | 0.7            |
| Certification               | -    | IEC 61215,    | IEC 61215,     | IEC 61215,     |
|                             |      | IEC 61730,    | IEC 61730,     | IEC 61730,     |
|                             |      | CE Certified, | IEC 62804,     | IEC 62716,     |
|                             |      | ISO 9001,     | ISO 9001,      | CE Certified,  |
|                             |      | ISO 14001     | ISO 14001      | TUV Certified  |

#### Table 77: Technical characteristics of PV modules

#### 16.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

#### 16.2.2. Inverter

Table 78 presents the main technical characteristics of the selected model.

| Parameter              | Unit | Schneider Electric          |
|------------------------|------|-----------------------------|
| Model                  | -    | Conext Core XC-680          |
| Max. efficiency        | %    | 98.9                        |
| Max. DC input voltage  | V    | 1000                        |
| Max. DC current        | А    | 1280                        |
| MPPT operating voltage | V    | 550 to 800                  |
| range                  |      |                             |
| Number of MPP          | no.  | -                           |
| independent inputs     |      |                             |
| Max. AC output power   | kW   | 680                         |
| Nominal AC voltage     | V    | 380                         |
| Certification          | -    | IEC 61000, IEC62103, IEC    |
| (IEC/IEEE/EN)          |      | 61727, IEC62116, IEC 62109. |

 Table 78: Technical characteristics of Inverter



#### 16.2.2.1. Warranty

Table 79 presents the Inverter product warranty:

| Make                                     | Warranty |  |
|--|----------|--|
| Schneider Electric<br>Conext Core XC-680 | 5 years  |  |

### 16.2.3. Inverter Duty Transformer

Table 80 presents the key technical characteristics of the selected Raychem transformer.

| Parameter                  | Unit | Raychem                           | Raychem                        |
|----------------------------|------|-----------------------------------|--------------------------------|
| Rating                     | kVA  | 1400                              | 750                            |
| Туре                       |      | ONAN, Oil<br>Immersed,<br>Outdoor | ONAN, Oil Immersed,<br>Outdoor |
| Phases                     | No.  | 3                                 | 2                              |
| Frequency                  | Hz   | 50                                | 50                             |
| Voltage                    | kV   | 0.38/0.38/11kV                    | 0.38/11kV                      |
| Windings                   | No.  | 3 (1 HV, 2 LV)                    | 2 (1 HV, 1 LV)                 |
| Vector Group               |      | Dyn11yn11                         | Dyn11                          |
| Impedance at principal tap | %    |                                   |                                |

#### Table 80: Technical characteristics of IDT

## 16.3. Project Design

### 16.3.1. DC Configuration

The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 12.4 MWp which is connected to 17 inverters of 10 MW cumulative capacity. 20 modules form a string and there are a total of 1,979 strings. The fixed tilt Module Mounting Structure at 8° tilt angle has been considered. The DC to AC ratio for inverters are 1.2. Figure 68 show the actual photographs of PV array area.



Figure 68: Solar PV array




### 16.3.2. AC Configuration

As per the information provided by the Client, there are 16 nos. of inverters of 680 kW each connected to the inverter duty transformer (IDT) of suitable rating which step up the voltage to 33 kV. The output of every two IDT is connected to 33 kV RMU panel. All RMU panels are equipped with all necessary protection system which includes both transformer electrical and mechanical protections. All RMU panel interconnected with each other. The combined power further evacuated to main 33 kV switchgear panel at site via 2 no's of cable feeders. The 33 kV main HT panel has two incoming cable feeders from RMU panels and one outgoing cable feeder. The 33 kV switchgear panel are equipped with all necessary protection devices.

### 16.4. Power evacuation

The combined generated 10 MW power at 33 kV further converted from cable feeder to overhead line feeder with the help of double pole structure. The combined power further evacuated to 132 kV Rora, Lalitpur Grid Substation via 33 kV transmission line. The transmission line length is 8 km.

#### Figure 69: Power Evacuation Schematic





### 17. TL Nangla

### 17.1. About Project

The Project is located at Nangla Village, District Bhatinda, Punjab state of India. The Project was constructed by EPC Contractor; M/s. Belectric and has been operational since 24<sup>th</sup> March 2015. Currently the O&M contractor is Mitarsh Energy.

The Project is situated 50 km away from Bhatinda district headquarters. The nearest railway station is at Bhatinda railway which is around 50 km away from the site. The nearest airport to the project site is at Chandigarh Airport which is 215 km away. The Project site is well connected.



Figure 70: TL Nangla





### Figure 71: TL Nangla- Satellite image of project layout

### 17.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 81.

| Component | Make and Model                   | Quantity |
|-----------|----------------------------------|----------|
| Module    | First Solar FS-395               | 44205    |
| Inverter  | SMA Sunny Central 900CP XT       | 4        |
| IDT       | Raychem 2 MVA, 0.405/0.405/11 kV | 2        |

#### Table 81: Summary of key components

### 17.2.1. PV modules

Table 82 presents the main technical characteristics of the installed PV modules.

| Table 82: Technical characteristics of PV module |     |             |  |  |
|--|-----|-------------|--|--|
| Parameter  | UoM | First Solar |  |  |
| Technology                                       |     | Thinfilm    |  |  |
| Peak power (Pmax)                                | W   | 95          |  |  |
| Voltage at Pmax (Vmpp)                           | V   | 45.8        |  |  |
| Current at Pmax (Impp)                           | А   | 2.08        |  |  |



| Parameter                   | UoM  | First Solar  |
|-----------------------------|------|--|
| Open Circuit Voltage (Voc)  | V    | 58.0   |
| Short Circuit Current (Isc) | А    | 2.29   |
| Maximum system voltage      | V    | 1000   |
| Temp coefficient of Pmax    | %/°C | -0.29  |
| Degradation                 | %    | 0.7%   |
| Certification               | -    | IEC 61646, IEC61730,<br>TUV certified, CE<br>Certified, ISO 9001 |

### 17.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

### 17.2.2. Inverter

Table 83 presents the main technical characteristics of the selected model.

| Parameter              | Unit | SMA                     |
|------------------------|------|-------------------------|
| Model                  | -    | Sunny Central 900CP XT  |
| Max. efficiency        | %    | 98.6                    |
| Max. DC input voltage  | V    | 1,000                   |
| Max. DC current        | А    | 1,400                   |
| MPPT operating voltage | V    | 656 to 850              |
| range                  |      |                         |
| Number of MPP          | no.  | 1                       |
| independent inputs     |      |                         |
| Max. AC output power   | kW   | 900                     |
| Max. DC current        | А    | 1411                    |
| MPPT operating voltage | V    | 405                     |
| range                  |      |                         |
| Certification          | -    | EN 61000,               |
| (IEC/IEEE/EN)          |      | EMC- Conformity,        |
|                        |      | CE Certified, IEEE 1547 |

#### Table 83: Technical characteristics of Inverter

#### 17.2.2.1. Warranty

Table 84 presents the Inverter product warranty:

| Table 84: Inverter warrant | у |
|----------------------------|---|
|----------------------------|---|

| Make                       | Warranty |
|----------------------------|----------|
| SMA Sunny Central 900CP XT | 5 years  |



### 17.2.3. Inverter Duty Transformer

Table 85 presents the key technical characteristics of the selected Raychem transformer.

| Table 05. Technical characteristics of IDT |      |                             |  |  |
|--|------|-----------------------------|--|--|
| Parameter                                  | Unit | Raychem                     |  |  |
| Rating                                     | kVA  | 2000                        |  |  |
| Туре                                       |      | ONAN, Oil Immersed, Outdoor |  |  |
| Phases                                     | No.  | 3                           |  |  |
| Frequency                                  | Hz   | 50                          |  |  |
| Voltage                                    | kV   | 0.405/0.405/11 kV           |  |  |
| Windings                                   | No.  | 3 (1 HV, 2 LV)              |  |  |
| Vector Group                               |      | Dy11y11                     |  |  |
| Impedance at principal tap                 | %    | 5.95                        |  |  |

#### Table 85: Technical characteristics of IDT

## 17.3. Project Design

### 17.3.1. DC Configuration

The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 4.2 MWp which is connected to 2 inverters of 4 MW cumulative capacity. 15 modules form a string and there are a total of 2,979 strings. The fixed tilt Module Mounting Structure at 15° tilt angle has been considered. The DC to AC ratio for inverters are 1.05. Figure 72 show the actual photographs of PV array area.

#### Figure 72: Solar PV array



### 17.3.2. AC Configuration

As per the submitted SLD for there are 4 nos. of inverters which are connected to the 2 nos. of three winding IDT of 2 MVA, 0.405/0.405/11 kV rating. The output of every two IDT is connected to 33 kV RMU panel. All RMU panels are equipped with all necessary protection system which includes both transformer electrical and mechanical protections. All RMU panel interconnected with each other. The




combined power further evacuated to main 11 kV switchgear panel at site. The 11 kV main HT panel has two incoming cable feeders from RMU panels and one outgoing cable feeder. The 11 kV switchgear panel are equipped with all necessary protection devices.

## 17.4. Power evacuation

The combined generated 10 MW power at 11 kV further converted from cable feeder to overhead line feeder with the help of double pole structure. The combined power further evacuated to Grid Substation via 11 kV transmission line.

#### Figure 73: Power Evacuation Schematic



### 18. TL Tinwari


### 18.1. About Project

The Project is located at Tinwari Village, District Jodhpur, Rajasthan state of India. The Project was constructed by EPC Contractor; M/s. Juwi and has been operational since 15<sup>th</sup> October 2011. Currently the O&M contractor is Meera.

The Project is situated 50 km away from Jodhpur district headquarters. The nearest railway station is at Jodhpur railway which is around 45 km away from the site. The nearest airport to the project site is at Jodhpur Airport which is 48 km away. The Project site is well connected.



#### Figure 74: TL Tinwari



## 18.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 86.

#### Table 86: Summary of key components

| Component | Make and Model                      | Quantity |
|-----------|-------------------------------------|----------|
| Module    | First Solar FS-380                  | 64,800   |
|           | First Solar FS-4115A                | 5,709    |
| Inverter  | SMA Sunny Central 630CP XT          | 8        |
| IDT       | Raychem 1.25 MVA, 0.315/0.315/33 kV | 4        |

### 18.2.1. PV modules

Table 87 presents the main technical characteristics of the installed PV modules.

#### Table 87: Technical characteristics of PV modules

| Parameter                   | UoM | First Solar | First Solar |
|-----------------------------|-----|-------------|-------------|
| Technology                  |     | Thinfilm    | Thinfilm    |
| Peak power (Pmax)           | W   | 80          | 115         |
| Voltage at Pmax (Vmpp)      | V   | 48.5        | 69.3        |
| Current at Pmax (Impp)      | А   | 1.65        | 1.66        |
| Open Circuit Voltage (Voc)  | V   | 60.8        | 87.6        |
| Short Circuit Current (Isc) | А   | 1.88        | 1.83        |



| Parameter                | UoM  | First Solar  | First Solar  |
|--------------------------|------|--|--|
| Maximum system voltage   | V    | 1000   | 1000   |
| Temp coefficient of Pmax | %/ºC | -0.29  | -0.28  |
| Degradation              | %    | 0.7%   | 0.7%   |
| Certification            | -    | IEC 61646,<br>IEC61730,<br>TUV certified,<br>CE Certified,<br>ISO 9001 | IEC 61646,<br>IEC61730,<br>TUV certified,<br>CE Certified,<br>ISO 9001 |

#### 18.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

### 18.2.2. Inverter

Table 88 presents the main technical characteristics of the selected model.

| Table 88: Technica | I characteristics of Inverter |
|--------------------|-------------------------------|
|--------------------|-------------------------------|

| Parameter                           | Unit | SMA  |
|-------------------------------------|------|--|
| Model                               | -    | Sunny Central 630CP XT                                   |
| Max. efficiency                     | %    | 98.6   |
| Max. DC input voltage               | V    | 1,000  |
| Max. DC current                     | А    | 1,350  |
| MPPT operating voltage range        | V    | 500 to 850   |
| Number of MPP<br>independent inputs | no.  | 1  |
| Max. AC output power                | kW   | 630  |
| Max. AC current                     | А    | 1,350  |
| MPPT operating voltage range        | V    | 315  |
| Certification<br>(IEC/IEEE/EN)      | -    | EN 61000,<br>EMC- Conformity,<br>CE Certified, IEEE 1547 |

#### 18.2.2.1. Warranty

Table 89 presents the Inverter product warranty:

#### Table 89: Inverter warranty

| Make                       | Warranty |
|----------------------------|----------|
| SMA Sunny Central 630CP XT | 5 years  |



### 18.2.3. Inverter Duty Transformer

Table 90 presents the key technical characteristics of the selected Raychem transformer.

| Parameter                  | Unit | Raychem                     |  |  |
|----------------------------|------|-----------------------------|--|--|
| Rating                     | kVA  | 1250                        |  |  |
| Туре                       |      | ONAN, Oil Immersed, Outdoor |  |  |
| Phases                     | No.  | 3                           |  |  |
| Frequency                  | Hz   | 50                          |  |  |
| Voltage                    | kV   | 0.315/0.315/33 kV           |  |  |
| Windings                   | No.  | 3 (1 HV, 2 LV)              |  |  |
| Vector Group               |      | Dyn11yn11                   |  |  |
| Impedance at principal tap | %    | 5                           |  |  |

#### Table 90: Technical characteristics of IDT

## 18.3. Project Design

### 18.3.1. DC Configuration

The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 5.84 MWp which is connected to 8 inverters of 5 MW cumulative capacity. 15 and 11 modules form a string and there are a total of 4,320 and 519 strings. The fixed tilt Module Mounting Structure at 20° tilt angle has been considered. The DC to AC ratio for inverters are 1.17. Figure 75 show the actual photographs of PV array area.

#### Figure 75: Solar PV array



### 18.3.2. AC Configuration

As per the submitted SLD for there are 8 nos. of inverters which are connected to the 4 nos. of three winding IDT of 1.25 MVA, 0.315/0.315/33 kV rating. The output of the two IDT is connected to 2-in-1-out 33 kV outdoor switchgear panel. The 2-in-1-out 33 kV outdoor switchgear panel have two incoming feeders from IDT and one outgoing to 3-in-1-out 33 kV switchgear panel. The 3-in-1-out 33 kV switchgear panel have two incoming feeders from IDT, one incoming from 2-in-1-out 33 kV switchgear




panel and one outgoing to 33 kV main switchgear panel ay MCR. All 33 kV switchgear panel are equipped with all necessary protection devices.

At MCR the 33 kV switchgear panel have one incoming feeder from PV plant side, one auxiliary transformer feeder and one outgoing feeder cable. The 33 kV switchgear panel are equipped with all necessary protection devices.

### 18.4. Power evacuation

The combined generated 5 MW power at 33 kV further converted from cable feeder to overhead line feeder with the help of double pole structure. The combined power further evacuated to Tinwari Grid Substation via 33 kV transmission line.

#### Figure 76: Power Evacuation Schematic



### 19. TL Gadna

### 19.1. About Project

The Project is located at Bap Village, District Jodhpur, Rajasthan state of India. The Project was constructed by EPC Contractor; M/s. Sun Bome services and has been operational since 20<sup>th</sup> March 2013. Currently the O&M contractor is Mitarsh Energy.

The Project is situated 176 km away from Jodhpur district headquarters. The nearest railway station is at Jodhpur railway which is around 170 km away from the site. The nearest airport to the project site is at Jodhpur Airport which is 180 km away. The Project site is well connected.



Figure 77: TL Gadna



### 19.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 91.

| Table 91. Outlindary of Rey components |                                       |          |  |  |  |
|--|---------------------------------------|----------|--|--|--|
| Component                              | Make and Model                        | Quantity |  |  |  |
| Module                                 | Nex Power NT-150 AF                   | 64,800   |  |  |  |
|  | Nex Power NT-155 AF                   |          |  |  |  |
|  | JA Solar JAP6-72-330/3BB              | 5,709    |  |  |  |
| Inverter                               | Schneider Electric Conext Core XC-680 | 7        |  |  |  |
|  | Sungrow SG-110-CX                     | 2        |  |  |  |
| IDT                                    | Raychem 1.4 MVA, 0.380/0.380/33 kV    | 4        |  |  |  |

#### Table 91: Summary of key components

### 19.2.1. PV modules

Table 92 presents the main technical characteristics of the installed PV modules.

| Parameter                  | UoM | Nex Power | Nex Power | JA Solar        |  |
|----------------------------|-----|-----------|-----------|-----------------|--|
| Technology                 |     | Thinfilm  | Thinfilm  | Polycrystalline |  |
| Peak power (Pmax)          | W   | 150       | 155       | 330             |  |
| Voltage at Pmax (Vmpp)     | V   | 64.7      | 65.2      | 37.65           |  |
| Current at Pmax (Impp)     | А   | 2.32      | 2.38      | 9.28            |  |
| Open Circuit Voltage (Voc) | V   | 85.5      | 85.5      | 46.40           |  |

#### Table 92: Technical characteristics of PV modules



| Parameter                   | UoM  | Nex Power   | Nex Power   | JA Solar  |
|-----------------------------|------|---|---|---|
| Short Circuit Current (Isc) | А    | 2.56  | 2.54  | 8.77  |
| Maximum system voltage      | V    | 1000  | 1000  | 1500  |
| Temp coefficient of Pmax    | %/ºC | -0.28   | -0.28   | -0.41   |
| Module efficiency           | %    | -   | -   | 17  |
| Degradation                 | %    | 0.7%  | 0.7%  | 0.7%  |
| Certification               | -    | IEC 61646,<br>IEC61730,<br>CE Certified,<br>ISO 9001<br>ISO 14001 | IEC 61646,<br>IEC61730,<br>CE Certified,<br>ISO 9001<br>ISO 14001 | IEC 61215,<br>IEC 61730,<br>CE Certified,<br>ISO 9001,<br>ISO 14001 |

#### 19.2.1.1. Warranty

According to the module datasheet, the limited product warranty covers PV modules for 10 years from the warranty start date against defects in materials and workmanship under normal application, installation, use, and service conditions. The linear performance warranty guarantees over power output at the end of 25<sup>th</sup> year.

### 19.2.2. Inverter

Table 93 presents the main technical characteristics of the selected model.

| Parameter                        | Unit | Schneider Electric   | Sungrow  |  |  |
|----------------------------------|------|--|--|--|--|
| Model                            | -    | Conext Core XC-680   | SG-110-CX  |  |  |
| Max. efficiency                  | %    | 98.9   | 98.7   |  |  |
| Max. DC input voltage            | V    | 1000   | 1100   |  |  |
| Max. DC current                  | А    | 1280   | 30   |  |  |
| MPPT operating voltage range     | V    | 550 to 800   | 550 to 800   |  |  |
| Number of MPP independent inputs | no.  | -  | 2  |  |  |
| Max. AC output power             | kW   | 680  | 110  |  |  |
| Nominal AC voltage               | V    | 380  | 320 – 460  |  |  |
| Certification<br>(IEC/IEEE/EN)   | -    | IEC 61000, IEC62103,<br>IEC 61727, IEC62116,<br>IEC 62109. | IEC 62109, IEC 61727,<br>IEC 62116, IEC 60068,<br>IEC 61683, |  |  |

#### Table 93: Technical characteristics of Inverter

#### 19.2.2.1. Warranty

Table 94 presents the Inverter product warranty:

#### Table 94: Inverter warranty

| Make                                  | Warranty |
|---------------------------------------|----------|
| Schneider Electric Conext Core XC-680 | 5 years  |
| Sungrow SG-110-CX                     | 5 years  |
|                                       |          |



### 19.2.3. Inverter Duty Transformer

Table 95 presents the key technical characteristics of the selected Raychem transformer.

| Table 35. Technical characteristics of ibi |                                       |  |  |  |
|--|---------------------------------------|--|--|--|
| Unit                                       | Raychem                               |  |  |  |
| kVA  | 1400                                  |  |  |  |
|  | ONAN, Oil Immersed, Outdoor           |  |  |  |
| No.  | 3                                     |  |  |  |
| Hz   | 50                                    |  |  |  |
| kV   | 0.380/0.380/33 kV                     |  |  |  |
| No.  | 3 (1 HV, 2 LV)                        |  |  |  |
|  |                                       |  |  |  |
| %  |                                       |  |  |  |
|  | Unit<br>kVA<br>No.<br>Hz<br>kV<br>No. |  |  |  |

#### Table 95: Technical characteristics of IDT

## 19.3. Project Design

### 19.3.1. DC Configuration

The design configuration for the project and has reviewed the module, string, and inverter configurations. The installed DC capacity of the project is 5.50 MWp which is connected to 10 inverters of 5 MW cumulative capacity. 10 and 18 modules form a string and there are a total of 3,404 and 42 strings. The fixed tilt Module Mounting Structure at 22° tilt angle has been considered. The DC to AC ratio for inverters are 1.1.Figure 78 show the actual photographs of PV array area.

#### Figure 78: Solar PV array





### 19.3.2. AC Configuration


As per the submitted SLD for there are 9 nos. of inverters which are connected to the 4 nos. of three winding IDT of 1.4 MVA, 0.380/0.380/33 kV and 1 no of two winding IDT of 750 kVA, 0.380/33 kV rating. The output of each IDT is connected 33 kV HT breaker. Each HT breaker further looped to other HT panels. There are four nos. of HT panels. The looped power further evacuated to 33 kV main HT panel.

The 33 kV main HT panel have two incoming feeders from PV plant side, one aux transformer feeder and outgoing feeder cable. The 33 kV switchgear panel are equipped with all necessary protection devices.

### 19.4. Power evacuation

The combined generated 5 MW power at 33 kV further converted from cable feeder to overhead line feeder with the help of six pole structure. The combined power further evacuated to XX Grid Substation via 33 kV transmission line.

#### Figure 79: Power Evacuation Schematic



### 20. TL GGEL

### 20.1. About Project

The Project is located at Nokh Village, District Jaisalmer, Rajasthan state of India. The Project was constructed by EPC Contractor; M/s. Lauren Engineering and has been operational since 9<sup>th</sup> March 2014. Currently the O&M contractor is by PS-2 Dhaleri.

The Project is situated 193 km away from Jaisalmer district headquarters. The nearest railway station is at Jaisalmer railway which is around 200 km away from the site. The nearest airport to the project site is at Jaisalmer Airport which is 210 km away. The Project site is well connected.





#### Figure 81: GGEL – Satellite image of project layout



## 20.2. Technology

TruBoard has reviewed the technology considered in the project. Summary of the key components installed in the project is indicated in Table 96.

| Table 96: | Summary | of key | components |
|-----------|---------|--------|------------|
|           |         |        |            |

| Component                                  | UoM | Quantity |
|--|-----|----------|
| Solar Field Area                           | m2  | 392,400  |
| Solar Field Loops (30 loops in each field) | No. | 120      |
| Length of collector per module             | М   | 12       |



| Component  | UoM | Quantity |
|--|-----|----------|
| Length of Solar Collector Assembly                         | М   | 148.5    |
| Aperture width   | М   | 5.76     |
| No. of Solar Collector Assembly per loop                   | No. | 4        |
| Number of Mirrors  | No. | 161,280  |
| HTF Outlet temperature                                     | °C  | 393.00   |
| HTF Inlet temperature                                      | °C  | 293.00   |
| Generator Output   | MWe | 50       |
| Auxiliary power requirement                                | %   | 10 – 11  |
| Auxiliary Transformer 7.5/9.375MVA, 10.5/6.6kV             | No. | 1        |
| 2.5/3.125MVA, 10.5/0.440kV                                 | No. | 2        |
| 1.5/1.725MVA, 6.6/0.440kV                                  | No. | 1        |
| 0.75/0.863MVA, 6.6/0.440kV                                 | No. | 1        |
| Emergency DG set of 1.5 MVA, 440 V                         | No. | 1        |
| Turbine Generator (TG) 50 MW                               | No. | 1        |
| Generator Step Up transformer (GSUT) of rating 45/60/75MVA | No. | 1        |

## 20.3. Project Design

The Solar Parabolic Trough field (SPTF) consists of 120 loops, with each loop having 4 Solar Collection Assemblies (SCA). Each SCA will include 12 trough collectors or Solar Collector Elements (SCE). Access to the mirrors for periodic washing has been provided.

Each SCE is 12m long and consists of 28 individual Parabolic Trough Mirrors. The Parabolic Trough Mirrors are arranged in four rows running the 12m long SCE. Each SCE is supported at its ends by pylons. The SCA is comprised of 12 SCE's. The combined overall length of the SCA is approximately 150m. Each Solar Collector Loop is comprised of 4 SCA's. The Solar Collector Loop is configured in a U-shape such that two (SCA's) collectors make up each leg of the U. Such configuration of thirty loops has been present which further resulting in 120 loops. The loops and fields are configured such that each loop and field operates in parallel with the others. The plant also includes drive systems, mirrors, receiver tubes, ball joints, HTF supply-and-return piping and manual isolation valves, the electrical power system, and instrumentation and controls to track movement of the sun and control the trough collectors' position to maximize collection of solar energy. Figure 82 show the actual photographs of PV collector area.

#### Figure 82: Solar PV collector





### 20.3.1. AC Configuration

The electrical system of the plant consists of solar island electricals and power block electricals. The solar island electricals include the power distribution for the solar collector arrays. The power block electricals include the generating unit, power evacuation system auxiliary power supply system, emergency power supply system, DC system, uninterrupted power supply system and its associated equipment. The power is generated using one number of Turbine Generator (TG) of 50MW capacity. The generator output voltage is 10.5 kV. which is stepped up to 132kV using a Generator Step Up transformer (GSUT) of rating 45/60/75MVA.

The power is evacuated through the 132kV line to 132/33kV GSS PS-2 substation of Rajasthan Rajya Vidyut Prasaran Nigam Lit., (RVPNL). The distance of the transmission line is 10.65km.

### 20.4. Power evacuation

The generated 50 MW power at 10.5 kV further stepped up to 132kV using a Generator Step Up transformer (GSUT) of rating 45/60/75MVA. The power is evacuated through the 132kV transmission line to 132/33 kV GSS PS-2 substation of Rajasthan Rajya Vidyut Prasaran Nigam Ltd., (RVPNL). The distance of the transmission line is 10.65 km.

#### Figure 83: Power Evacuation Schematic



# 21. Terralight Solar Energy SitamauSS Private Limited (TL SitamauSS)

The technical details of the assets of TL SitamauSS has not been provided for review. However, as per the information shared by the Client, "TL SitamauSS is engaged in the business of providing transmission and step-up services to its shareholder companies. The services provided by TL SitamauSS are essential and integral to the functioning of the solar plants owned by these shareholder companies. TL SitamauSS serves as an interconnection between the electricity delivery point and the electricity generating plant. Moreover, TL SitamauSS offers transmission services to four Special Purpose Vehicles (SPVs). Among these SPVs, two are owned by VRET (Globus and TL Patlasi), while the other two are owned by Brookfield (Focal Photovoltaic India Private Limited and Focal Renewable Energy Two India Private Limited). VRET hold a 66.06% ownership stake in TL SitamauSS through its SPVs, TL Patlasi and Globus, with each SPV owning 33.03%, the remaining balance is owned by Brookfield entities."



TruBoard Credit Monitoring Services Private Limited

Registered address: 307, Beach Heaven-I, Juhu Tara Road, Juhu, Mumbai – 400 049 Maharashtra, India

www.truboardpartners.com