

## Dhule Power Transmission Limited

### Amendment No. - 03 (Pre Bid Clarifications)

12.03.2026

**Subject: Implementation of 1 No. 220kV line bay at Dhule PS for interconnection of M/s Adyant Enersol Pvt. Ltd.(AdEPL) 94 MW RHGS**

| <b>Sl. No</b> | <b>Name of Document</b>                                 | <b>Existing Provision/Extract from Specification</b>                             | <b>Suggested texts for amendments/Query/Clarification Sought</b>   | <b>Rationale for Clarification/Amendments</b> | <b>DPTL Replies</b>  |
|---------------|---|--|--|---|--|
| 1             | Indicative Items (BOQ) Dhule Electrical - R0, Volume II | Line Item -P, Mandatory Spares as per CEA guidelines                             | Given that this is a single-bay extension only, the CEA-mandated spare requirements increase the project's capital expenditure. We believe providing 2 nos. spare of 220kV CTs/ CVTs/ LAs for supply of every 3 nos. units is excessive for this limited scope. Please provide reduced spare list. |   | Please consider as per CEA Mandatory Spare list.   |
| 2             | Indicative Items (BOQ) Dhule Electrical - R0, Volume II | Line Item -G Lightning Protection material for civil buildings inside Switchyard | There is no building extension or construction of new building, hence what is the reason to provide this line item.  |   | This point is for SPR room, if applicable.   |
| 3             | Volume II   | General  | Regarding the Dhule Substation 220kV Line Extn., Please confirm if the bidder is required to consider an AC Kiosk in the Switchyard to house the Control & Relay panels or same will be housed in an existing AC Kiosk in the switchyard nearby to the 220kV Line bay                              |   | Check the requirement as per existing Location of SPR. If distance is more, then consider SPR. |

