

Purulia & Kharagpur Transmission Company Limited

Amendment No. - 01 (Pre Bid Clarifications)

24.06.2026

Subject: Supply and Installation of OPGW (48F) along with required accessories and required Fiber Optic Terminal Equipment (FOTE) for commissioning of optical fiber links on ISTS line -: 400 kV D/C Kharagpur Chaibasa Transmission Line (Line Length: 161.67 Km)

Sl. No	Name of Document	Suggested texts for amendments/Query/Clarification Sought	PKTCL Replies
1	Volume II	Kindly provide Sag Tension Criteria for OPGW cable	Please find below: 1. Configuration: 400kV D/C <ul style="list-style-type: none">• Normal Span: 400 m• Wind Pressure: 198 kg/m²• Sag at 53°C (Nil Wind): 8.186 m• Sag at 32°C (Nil Wind): 7.575 m• Tension at EDT (32°C, Full Wind): To be matched with the sag values mentioned above

Purulia & Kharagpur Transmission Company Limited